


IAP Cover Sheet		Version Name: Period 11	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Approved By			
Incident Commander: Long, David			
<h1>Incident Action Plan</h1>			
IAP Cover Sheet		Prepared By Planning, Updated 05/20/2018 10:43 UTC -6:00 PP	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 1 of 118	© TRG

Table of Contents

Incident Name: 2018 Superior Refinery Fire
--

Period: Period 11 [05/23/18 06:00 - 05/30/18 06:00]

<i>Report Name</i>	<i>Page</i>
IAP Cover Sheet	1
Weather Report	3
Map/Sketch	4
ICS 202 - Incident Objectives	8
ICS 202b - Critical Information Requirements	10
ICS 204 - Assignment List	11
ICS 205 - Radio Communications	56
ICS 205a - Communications List	57
ICS 206 - Medical Plan	58
ICS 207 - Organization Chart	66
ICS 208 - Site Safety Plan	68
Main Column Overhead Receiver De-Inventory Plan	71
Waste Management Plan (Amended)	112
Community Air Monitoring Reduction Plan	116
Community Soot Assessment Work Plan	117

Table of Contents

Weather Report			Version Name: 20180522_1600		
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]		
Present Conditions					
Weather Conditions as of 05/22/2018 15:18					
superior, wi us station id: MID_KSUW					
Humidity (%): 47 Wind Speed: 12 mph Wind Direction (from): W Temperature: 78 Fahrenheit Visibility: 10 mile(s)			Pressure: 29.97 psi Dew Point: 56 Feels Like: 78 UV Index:		
Cloudy					
Forecast Date	Wind	Temp High/Low	% Precip	Sunrise/Sunset	Notes
Tue 05/22/2018	5 mph SW	49 F	10		Partly cloudy, with a low around 49. Southwest wind around 5 mph.
Wed 05/23/2018	5 mph E	75 F	10		Sunny, with a high near 75. Light and variable wind becoming east 5 to 10 mph in the morning.
	5 mph E	48 F	40		A chance of thunderstorms after 1am. Increasing clouds, with a low around 48. East wind 5 to 10 mph. Chance of precipitation is 40%.
Thu 05/24/2018	10 mph SE	74 F	20		A slight chance of thunderstorms. Partly sunny, with a high near 74. East wind 5 to 10 mph becoming south in the afternoon. Winds could gust as high as 15 mph. Chance of precipitation is 20%.
	7 mph S	55 F	50		A chance of thunderstorms. Mostly cloudy, with a low around 55. South wind 5 to 10 mph. Chance of precipitation is 50%.
Fri 05/25/2018	8 mph SW	81 F	30		A chance of thunderstorms, mainly after 1pm. Partly sunny, with a high near 81. Chance of precipitation is 30%
	7 mph SW	53 F	20		Partly cloudy, with a low around 53.
Tides					
Weather Report			Prepared By Situation Unit, Updated 05/22/2018 15:28 UTC -6:00 PP		
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 3 of 118		© TRG	


Incident Map/Sketch

20180521_Processing Plant Imagery



Incident Map/Sketch

20180522_Active Zones Map



Incident Map/Sketch

20180522_Map for Crane Operations



ICS 202 - Incident Objectives		Version Name: Period 11	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Objective(s)			
Ensure the Safety of the public and Refinery Personnel			
Incident stabilization			
Evidence Preservation			
Minimize environmental impacts			
Keep Stakeholders Informed of Response Activities			
Monitor social and local media			
Operational Period Command Emphasis (Safety Message, Priorities, Key Decisions/Directions)			
Limitations and Constraints <ul style="list-style-type: none"> Weather Conditions Night Operations (Limited) Limited Utilities (Electricity, Instrumentation, Air, Steam, WWTP, sewer system) Spilled Material Characteristics (monitoring/PPE requirements) Public Health Concerns Community/Media Perception Evidence Preservation / accessibility Work/rest Rotation Requirements Disposal of Waste Extent of damage Site access & hazards Site congestion / SIMOps 			
Key Decisions <ul style="list-style-type: none"> IC - Husky Name of Incident = 2018 Superior Refinery Fire Overall Response Organization - Staffing (C&G Staff filled by Husky)? <p>(Note: Section chiefs have full authority on filling positions however make sure that agencies are integrated into the organization)</p> <ul style="list-style-type: none"> Command Post – Superior City Center (1409 Hammond Ave, Superior, WI 54880) Operational Period & work hours - 7 days (5/23/18 0600hr - 5/30/18 0600hr) Maintanance will go to 2 shifts of 10hrs each [Sunday Critical Path items only] All external releases of information should be approved by ICS Safe work plans associated with Critical activities Incorporate select task forces into regular operations 			
Procedures <ul style="list-style-type: none"> Resource Requests / Ordering Procedures (213RR Process) / Demob 221 Documentation Process & Guidelines Claims Process (1-855-527-5002) 			
Incident Action Plan Components			
<input checked="" type="checkbox"/>	IAP Cover Sheet	<input checked="" type="checkbox"/>	Weather Report
<input checked="" type="checkbox"/>	Map/Sketch	<input checked="" type="checkbox"/>	ICS 202 - Incident Objectives
<input checked="" type="checkbox"/>	ICS 202b - Critical Information Requirements	<input checked="" type="checkbox"/>	ICS 204 - Assignment List
<input checked="" type="checkbox"/>	ICS 205 - Radio Communications	<input checked="" type="checkbox"/>	ICS 205a - Communications List
ICS 202 - Incident Objectives		Prepared By Planning, Updated 05/22/2018 16:30 UTC -6:00 PP	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 8 of 118	© TRG

ICS 202 - Incident Objectives

Version Name: Period 11

Incident Name: 2018 Superior Refinery Fire
--

Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]

<input checked="" type="checkbox"/>	ICS 206 - Medical Plan	<input checked="" type="checkbox"/>	ICS 207 - Organization Chart
<input checked="" type="checkbox"/>	ICS 208 - Site Safety Plan	<input checked="" type="checkbox"/>	Main Column Overhead Receiver De-Inventory Plan
<input checked="" type="checkbox"/>	Waste Management Plan (Amended)	<input checked="" type="checkbox"/>	Community Air Monitoring Reduction Plan
<input checked="" type="checkbox"/>	Community Soot Assessment Work Plan		

ICS 202 - Incident Objectives

Prepared By Planning, Updated 05/22/2018 16:30 UTC -6:00 PP

ICS 202b - Critical Information Requirements		Version Name: Period 11	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
<h2>Incident Command - Critical Threshold Reporting Criteria</h2> <p>** If any of these conditions are met, Incident Commander must be notified immediately **</p> <ul style="list-style-type: none">• Injury or Death (OSHA/1st Aid or greater through Safety Officer)• Significant change of status of site conditions• Public health impacts• Impacted sensitive areas beyond protection/Any change to trajectories• Loss of major tactical resources• Unplanned VIP visits en-route/planning/arriving• Adverse protest plans or interview requests• Adverse political/influence• Loss or breach of containment• Any breach in safety/investigation zone• Special requests from agencies• Any changes to respiratory requirements (eg: SCBA)• Any evidence of wildlife impact• Any exceedance of an air monitoring action level			
ICS 202b - Critical Information Requirements		Prepared By Planning, Updated 05/20/2018 14:03 UTC -6:00 PP	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 10 of 118	© TRG

ICS 204 - Assignment List			Task Force: De-Inventory Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Stabilization Group Supervisor	Thom, Tim	Husky Energy Inc.	715-817-8016	
De-Inventory Task Force	Laszewski, Aaron	Husky Energy Inc.	920-883-1992	
De-Inventory Task Force	Ivanca, Erin	Husky Energy Inc.	651-592-6339	
De-Inventory Task Force	Campbell, Adam	Husky Energy Inc.	218-491-4920	
De-Inventory Task Force Leader	Witherill, Troy	Husky Energy Inc.	218-522-0114	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
De-Inventory Task Force	Manpower: Responder	Day Shift Responders	2	
De-Inventory Task Force	Manpower: Responder	Engineer	7	
De-Inventory Task Force	Manpower: Responder	Project Manager	1	
De-Inventory Task Force	Manpower: Responder	Project Control	1	
De-Inventory Task Force	Equipment: Safety	VCU	2	
De-Inventory Task Force	Manpower: Responder	Contractors	29	
ICS 204 - Assignment List			Updated 05/07/2018 17:09 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 11 of 118	© TRG	

ICS 204 - Assignment List		Task Force: De-Inventory Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Assignments			
<p>De-inventory the following units as per approved plan:</p> <ul style="list-style-type: none"> - Platformer - High pressure receiver and condensers - Propane treater and sand filter - ISOM <p>Continue to develop the hydrocarbon de-inventory plans for priority assets:</p> <ul style="list-style-type: none"> - FCC Gas con stripper & debutanizer - ISOM - #2 Hydrobon - #2 DUF - North Crude - High pressure receiver and condensers - Propane treater and sand filter - C3/C4 merox and amine contactor <p>SRS/Evergreen to assist with plan development.</p> <p>De-Inventory fuel products upon completion of pipeline control system activation.</p> <p>Develop plan to tie in natural gas to asphalt tank farm.</p> <p>**No operations on additional units until final approvals have been completed**</p> <p>Hydrocarbon de-inventory plan for each unit will be approved by the following:</p> <ul style="list-style-type: none"> - Incident Commander - Operations Section Chief - Planning Section Chief - Environmental Unit Leader - Safety Officer - Lead Investigator 			
Communications			
Name / Function		Contact Details	
ERT Channel		8	
Channel 1 Talk Around		11	
Primary		1	
Secondary		2	
Radio		3 to 7	
Special Environmental Considerations			
<p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Prior to commencing de-inventory activities, notify GHD so task specific monitoring can commence to verify site and public safety. Once de-inventory events commence, notification of any venting/release of vapor/liquid hydrocarbon to the environment shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p> <p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p>			
ICS 204 - Assignment List		Updated 05/07/2018 17:09 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 12 of 118	© TRG

ICS 204 - Assignment List		Task Force: De-Inventory Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>Refer to individual De-inventory safety plans for additional requirements.</p> <p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Ensure that air monitoring, including 4-Gas and product specific (Benzene, Hydrogen Sulfide, etc.) is done during the de-inventory process.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Be cognizant of the hazards of the hazards of Nitrogen, unit contents including Benzene, H2S, petroleum products, etc.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
<div></div>			
ICS 204 - Assignment List		Updated 05/07/2018 17:09 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 13 of 118	© TRG

ICS 204 - Assignment List			Task Force: Chemical Removal Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Stabilization Group Supervisor	Thom, Tim	Husky Energy Inc.	715-817-8016	
Chemical Removal Task Force Leader	McCusker, Brian	Husky Energy Inc.	218-348-9769	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Chemical Removal Task Force	Manpower: Responder	Day Shift Responders	4	
Chemical Removal Task Force	Manpower: Responder	Night Shift Responders	7	
Assignments				
<p>Operations will:</p> <ul style="list-style-type: none"> - Continue HF air monitoring. - Maintain deluge system around HF tank. - Implement assignments per the store in place bow tie action tracker. - Complete bow-tie risk analysis for neutralizing on-site. - Identify damaged cylinders. <p>**No additional operations until final approvals have been received**</p> <p>Four (4) options continue to be developed in parallel by HF Alkylation Consultants and SPSI in order to evaluate and mitigate risk:</p> <ol style="list-style-type: none"> 1) Neutralize on-site 2) Transfer to an off-site facility 3) Retain on-site with safeguards in place 4) Other safe management alternatives 				
Communications				
Name / Function		Contact Details		
ERT Channel		8		
Channel 1 Talk Around		11		
Primary		1		
Secondary		2		
Radio		3 to 7		
Special Environmental Considerations				
<p>All precautions should be taken to minimize release of any chemical to the environment. If chemical is released the environmental unit leader shall be notified immediately. Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly. Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring. Any liquid hydrocarbon release shall be cleaned up immediately.</p>				
ICS 204 - Assignment List			Updated 05/11/2018 15:20 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 14 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Chemical Removal Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>In Alky Unit, fixed HF air monitors do not currently work. Rely on personal HF monitors and area monitors for determination of HF within the air.</p> <p>In Alky Unit, the HF Mitigation System can now be operated from the FCC Control Room. Immediately contact the FCCU Control Room if portable air monitors alarm or if an HF leak is observed.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Be cognizant of the hazards of the products being handled including hydrofluoric acid and other hazards of the Alkylation Unit.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
ICS 204 - Assignment List		Updated 05/11/2018 15:20 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 15 of 118	© TRG

ICS 204 - Assignment List			Task Force: Steam Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Stabilization Group Supervisor	Thom, Tim	Husky Energy Inc.	715-817-8016	
Steam Task Force Leader	Amato, Joe	Husky Energy Inc.	715-969-7724	
Steam Task Force Leader	Smith, Doug	Nexus Engineering	419-346-5987	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Steam Task Force	Manpower: Responder	Day Shift Responders	3	
Steam Task Force	Manpower: Responder	Engineer	1	
Steam Task Force	Manpower: Responder	Project Manager	1	
Assignments				
<p>Develop plan to re-instate steam on site to enable long term preservation of assets. Plan to include evaluation of bring on site package boiler and associated permits.</p> <p>Identify safe isolation and tie in points for packaged boiler.</p> <p>Implement steam re-instatement as per approved plan.</p> <p>Finalized Plan to be reviewed and approved by:</p> <ul style="list-style-type: none"> - Operations Section Chief - Planning Section chief - Safety Officer - Environmental Unit Lead - Incident Commander <p>**No operations to proceed prior to approval and permits in place**</p>				
Special Environmental Considerations				
If temporary boiler is needed a permit/exemption letter from the WDNR will need to be obtained prior to bringing it on-site.				
ICS 204 - Assignment List			Updated 05/14/2018 11:49 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 16 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Steam Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>When working along the refinery perimeter, be cognizant of slip, trip and fall hazards.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
ICS 204 - Assignment List		Updated 05/14/2018 11:49 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 17 of 118	© TRG

ICS 204 - Assignment List			Task Force: Pyrophoric Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Stabilization Group Supervisor	Thom, Tim	Husky Energy Inc.	715-817-8016	
Pyrophoric Task Force Leader	McCusker, Brian	Husky Energy Inc.	218-348-9769	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Pyrophoric Task Force	Foreman	Foreman	2	
Assignments				
<p>Identify the high-risk areas for iron sulfide and mitigation measures.</p> <p>Install nitrogen blanket on crude unit main fractionator.</p> <p>Maintain nitrogen blankets on:</p> <ul style="list-style-type: none"> - FCCU Main column - SRU / TGTU 				
Special Environmental Considerations				
<p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p>				
<div> <div>ICS 204 - Assignment List</div> <div>Updated 05/22/2018 10:11 UTC -6:00</div> </div>				
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 18 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Pyrophoric Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Be cognizant of the hazards of the products being handled.</p> <p>If working along the perimeter fence or other Husky property outside of refinery, contact security guards at 715-398-8220 to make them aware of your presence. Otherwise, the police will be called.</p> <p>When working along the refinery perimeter, be cognizant of slip, trip and fall hazards.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>Be sure to wear a life jacket when working over water. Life jackets are available in the Warehouse.</p> <p>Inspect for ticks when traveling in grassy or wooded areas.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
ICS 204 - Assignment List		Updated 05/22/2018 10:11 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 19 of 118	© TRG

ICS 204 - Assignment List			Task Force: Energy Restoration Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Mechanical Group Supervisor	Rikkola, Ken	Husky Energy Inc.	218-343-9538	
Energy Restoration Task Force Leader	Carlson, Brad	Husky Energy Inc.	218-390-5182	
Energy Restoration Task Force Leader	Massie, Nik	Husky Energy Inc.	715-817-1209	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Energy Restoration Task Force	Manpower: Responder	Electricians	10	
Energy Restoration Task Force	Supervisor	Supervisor	2	
Assignments				
<p>1) Submit plan for energizing the following areas:</p> <ul style="list-style-type: none"> - Plan to provide permanent power to VV building. - T building - Electrical plan to De-Inventory crude. - Plan to secure I building TAP. - M Building - Rail yard lights <p>2). Energize the following areas:</p> <ul style="list-style-type: none"> - VV building. - T building - De-Inventory crude unit. - Securing I building TAP. - Marketing loading dock lighting - M Building - Rail yard lights <p>3) Disconnect high voltage to hot zone per the approved plan.</p> <p>**Prioritization changes to plans need to be approved by Operations Section Chief**</p> <p>Plans to be approved through normal refinery MOC process, Operations Section Chief and Incident Investigation Team (Shane Strang)</p>				
Communications				
Name / Function		Contact Details		
ERT Channel		8		
Channel 1 Talk Around		11		
Primary		1		
Secondary		2		
Radio		3 to 7		
ICS 204 - Assignment List			Updated 05/22/2018 10:12 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 20 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Energy Restoration Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Environmental Considerations			
<p>Considerations of potential hydrocarbon release should be made prior to energizing hydrocarbon containing equipment or their control system in order to minimize the release of hydrocarbons.</p> <p>Prior to energizing any CEM buildings all building analyzers and sampling equipment shall be turned off.</p> <p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring. Any liquid hydrocarbon release shall be cleaned up immediately.</p>			
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Follow Refinery Electrical Safety and Lockout Tagout programs.</p> <p>Be aware of your surroundings. There may be large equipment and overhead work in your area.</p> <p>Be cognizant of downed power lines, overhead hazards and potential for unintentional energization of electrical equipment.</p> <p>Wear PPE appropriate to the potential electrical energy.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
ICS 204 - Assignment List		Updated 05/22/2018 10:12 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 21 of 118	© TRG

ICS 204 - Assignment List			Task Force: Control System Task Force		
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]		
Operations Personnel					
Position	Name	Affiliation	Contact Number(s)	Work Shift	
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161		
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594		
Mechanical Group Supervisor	Rikkola, Ken	Husky Energy Inc.	218-343-9538		
Control System Task Force Leader	Johnson, Joe	Husky Energy Inc.	651-307-7833		
Resources Required					
Area Of Operation	Resource Kind	Description	Quantity	Size	
Control System Task Force	Manpower: Responder	Electricians	1		
Control System Task Force	Manpower: Responder	Manpower: Responder	5		
Assignments					
<p>Install fiber cable to connect new crude control room to "T" building – to support DCS connection when it is available.</p> <p>Restore BOHO DeltaV DCS control, with approval from Investigation Task Force.</p> <p>Restore Pipeline Leak Detection and Spill Mitigation System.</p> <p>Restore LPG Bullet Area Monitors and Remote Deluge System.</p> <p>Energize PLC for Deluge Fire pump to enable pressure activation.</p> <p>Verify instrumentation wiring status on the following areas:</p> <ul style="list-style-type: none"> - Flare - Cooling water - Fuel gas - Steam - Instrument air - SRU - Crude unit - Platformer - TGTU - #2 Hydrobon 					
Special Environmental Considerations					
Ensure that HF Air Monitoring is intergrated with GHD program.					
<div>ICS 204 - Assignment List</div> <div> <div>INCIDENT ACTION PLAN SOFTWARE™</div> <div>Printed 05/22/2018 17:18 UTC -6:00</div> </div> <div> <div>Page 22 of 118</div> <div>Updated 05/10/2018 14:17 UTC -6:00</div> </div> <div>© TRG</div>					

ICS 204 - Assignment List		Task Force: Control System Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Be cognizant of the hazards of the products being handled including hydrofluoric acid and other hazards of the Alkylation Unit.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
<div></div>			
ICS 204 - Assignment List		Updated 05/10/2018 14:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 23 of 118	© TRG

ICS 204 - Assignment List			Task Force: Asset Stabilization Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Mechanical Group Supervisor	Rikkola, Ken	Husky Energy Inc.	218-343-9538	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Asset Stabilization Task Force	Manpower: Responder	Manpower: Responder	16	
Asset Stabilization Task Force	Manpower: Operator	Manpower: Operator	2	
Asset Stabilization Task Force	Equipment: Heavy	Crane	2	
Assignments				
<p>Primary asset of concern for asset stabilization: Stripper tower (15G-V10)</p> <p>Actions for stripper tower stabilization:</p> <ul style="list-style-type: none"> - 3D scan. - Submit cut plan. <p>Continue identifying other assets of concern including building integrity issues.</p> <p>Finalized Plan to be reviewed & approved by:</p> <ul style="list-style-type: none"> - Operations Section Chief - Planning Section Chief - Safety Officer - Environmental Unit Lead - Investigation Lead - Incident Commander <p>**No Operations to Proceed Prior to Plan Approval**</p>				
Communications				
Name / Function		Contact Details		
ERT Channel		8		
Channel 1 Talk Around		11		
Primary		1		
Secondary		2		
Radio		3 to 7		
Special Environmental Considerations				
<p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Once stabilization events commence, notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring. Actions shall be taken to minimize any release of hydrocarbons to the environment.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p>				
ICS 204 - Assignment List			Updated 05/22/2018 10:14 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 24 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Asset Stabilization Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>All contractors must be preapproved by Refinery Safety Department.</p> <p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Be cognizant of the hazards of the product in the vessel, fire and similar hazards.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request lighth plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221			
ICS 204 - Assignment List		Updated 05/22/2018 10:14 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 25 of 118	© TRG

ICS 204 - Assignment List	Task Force: Asset Stabilization Task Force
Incident Name: 2018 Superior Refinery Fire	Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]
20180522_Map for Crane Operations	



ICS 204 - Assignment List			Task Force: Asphalt Removal Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Mechanical Group Supervisor	Rikkola, Ken	Husky Energy Inc.	218-343-9538	
Asphalt Removal Task Force Leader	Stokes, Dave	Stack Brothers Mechanical	218-221-6427	
Asphalt Removal Task Force Leader	Linge, Jeremy	Husky Energy Inc.		
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Asphalt / Asbestos Removal Task Force	Manpower: Responder	Manpower: Responder	16	
Asphalt / Asbestos Removal Task Force	Front-end loader	Front-end loader	2	
Asphalt / Asbestos Removal Task Force	Manpower: Operator	Manpower: Operator	4	
Asphalt / Asbestos Removal Task Force	Roll Off Box	Roll Off Box	12	
Asphalt / Asbestos Removal Task Force	Vehicle	Roll Off Truck	2	
Asphalt / Asbestos Removal Task Force	Trackhoe	Trackhoe	1	
Asphalt / Asbestos Removal Task Force	Backhoe	Backhoe	1	
Asphalt / Asbestos Removal Task Force	Skid Steer	Skid Steer	1	
Asphalt / Asbestos Removal Task Force	Equipment: Heavy	Font-end Loader	2	
Assignments				
<p>Remove asphalt in priority areas as directed by operations and approved by Baker Risk.</p> <p>Provide access to facility components through asbestos containment and/or removal.</p> <p>Presumed asbestos containing material removal will be done by certified asbestos workers.</p> <p>Asbestos workers will implement "Asbestos Remediation Plan 2018 Superior Refinery Fire" that GHD produced.</p> <p>Aerial mapping of progress is completed twice weekly. Updated maps will be provided by OSC.</p> <p>Prioritize the removal areas on a map per operations.</p> <p>**Baker Risk needed for documentation and storage of evidence found**</p>				
Special Environmental Considerations				
<p>Follow existing waste management plan and approved by applicable agencies. Actions shall be taken to minimize any release of hydrocarbons to the environment. Any hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any hydrocarbon release shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p>				
ICS 204 - Assignment List			Updated 05/08/2018 15:40 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 27 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Asphalt Removal Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Any disturbance of Presumed Asbestos Containing Materials must be done by asbestos licensed personnel.</p> <p>Be cognizant of the hazards of the areas that you are working in. Certain areas, such as the HF Unit, may require additional PPE.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
ICS 204 - Assignment List		Updated 05/08/2018 15:40 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 28 of 118	© TRG

ICS 204 - Assignment List			Task Force: Inspection Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Mechanical Group Supervisor	Rikkola, Ken	Husky Energy Inc.	218-343-9538	
Inspection Task Force Leader	Debevc, Ed	Husky Energy Inc.	250-961-2357	
Inspection Task Force Leader	Johnston, Gary	Husky Energy Inc.	715-817-1131	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Inspection Task Force	Manpower: Responder	Manpower: Responder	10	
Assignments				
<p>1) Primary focus on the Crude Vac unit addressing the following areas.</p> <p>Engineering Drawings</p> <ul style="list-style-type: none"> - Assemble engineering package - Assemble database and baseline information <p>2) Work ahead of De-Inventory assignments to conduct visual assessment of additional equipment outside the known event areas.</p> <ul style="list-style-type: none"> - Inspect the asphalt tank farm for de-inventory. - Complete a visual impact assessment on ALKY unit. - Complete monthly inspection of ALKY fresh acid storage tank. <p>3) Perform mechanical integrity analysis on structures identified by the Investigation Task Force.</p> <p>4) Stress engineering to asses FCC main stack, NAPTHA splitter and main column.</p> <p>**Plan to be approved by Safety Officer, Operations Section Chief, Investigation Task Force Leader, Planning Section Chief and Incident Commander**</p>				
Special Environmental Considerations				
<p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p>				
ICS 204 - Assignment List			Updated 05/10/2018 14:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 29 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Inspection Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
<i>Special Site-Specific Safety Considerations</i>			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Be cognizant of the hazards of the product in reactor as well as nitrogen, fire and similar hazards.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
<i>Additional Information</i>			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
<div></div>			
ICS 204 - Assignment List		Updated 05/10/2018 14:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 30 of 118	© TRG

ICS 204 - Assignment List			Task Force: ERT Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Emergency Response Group Supervisor	Quimby, Jerome	Husky Energy Inc.	218-428-5190	
ERT Task Force Leader	Lozon, Mark	Husky Energy Inc.	218-590-8298	
ERT Task Force Leader	VanHornweder, Brian	Husky Energy Inc.	218-428-5210	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
ERT Task Force	Fire Fighting Foam	Fire Fighting Foam	1500	
ERT Task Force	Tanker Truck	Tanker Truck	1	
ERT Task Force	Foam pumper	Foam pumper	1	
ERT Task Force	Manpower: Responder	Manpower: Responder	20	
Assignments				
<p>Maintain 24hr readiness to respond to any incidents on-site. Follow guidelines as defined in existing Superior Refinery Emergency Response Plan.</p> <p>Deploy and maintain fire response to support de-inventorying, investigation and inspection activities.</p> <p>See attached map for warm and hot zone locations.</p> <p>ERT will ensure serviceability and organization of ERT building and equipment.</p>				
Communications				
Name / Function	Contact Details			
ERT Channel	8			
Channel 1 Talk Around	11			
Primary	1			
Secondary	2			
Radio	3 to 7			
Special Environmental Considerations				
<p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p>				
ICS 204 - Assignment List			Updated 05/22/2018 08:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 31 of 118	© TRG	

ICS 204 - Assignment List		Task Force: ERT Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
<div></div>			
ICS 204 - Assignment List		Updated 05/22/2018 08:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 32 of 118	© TRG

ICS 204 - Assignment List			Task Force: Fire Pump Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Emergency Response Group Supervisor	Quimby, Jerome	Husky Energy Inc.	218-428-5190	
Fire Pump Task Force Leader	Peterson, John	Husky Energy Inc.	218-428-6160	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Fire Pump Task Force	Manpower: Responder	Manpower: Responder	3	
Fire Pump Task Force	Pumps	Fire Pumps	3	
Assignments				
Maintain operational readiness of fire water pumps. Report any issues to the Emergency Response Group Supervisor.				
Communications				
Name / Function		Contact Details		
ERT Channel		8		
Channel 1 Talk Around		11		
Primary		1		
Secondary		2		
Radio		3 to 7		
Special Environmental Considerations				
Release of diesel fuel at the diesel fire water pumps shall be properly cleaned up immediately for proper disposal. Actions shall be taken to minimize any release of hydrocarbons to the environment.				
Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring.				
Special Site-Specific Safety Considerations				
Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots.				
If in Diesel Pump building and pumps are running, hearing protection must be worn.				
If working along the pond perimeter, a life jacket must be worn.				
Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.				
The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.				
Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.				
Additional Information				
If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221				
ICS 204 - Assignment List			Updated 05/07/2018 17:15 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 34 of 118	© TRG	

ICS 204 - Assignment List			Task Force: Security Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Security Task Force Leader	Brager, Lynn	Securitas	715-398-8220	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Security Task Force	Manpower: Responder	Manpower: Responder	18	
Security Task Force	Vehicle	Security Vehicle	4	
Assignments				
<p>Securitas to maintain 24hr security checkpoints at command post and control sites. Roving security to patrol between sites and to additional locations as requested.</p> <p>Security to reference list of (Non-Husky) individuals approved for access.</p> <p>Maintain temporary road blocks as directed by SOFR.</p>				
Communications				
Name / Function		Contact Details		
ERT Channel		8		
Channel 1 Talk Around		11		
Primary		1		
Secondary		2		
Radio		3 to 7		
Special Environmental Considerations				
<p>Immediate notification of a breach in the security of the site should be reported through the ICS system to mitigate the potential for a release of hydrocarbon to the environment. Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly. Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring. Any liquid hydrocarbon release shall be cleaned up immediately.</p>				
Special Site-Specific Safety Considerations				
<p>Any work on roadways requires a high visibility vest.</p> <p>Be cognizant of vehicle traffic.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>Park Vehicle for roadblocks so that your on not in oncoming traffics lane. If someone is not paying attention, they could potentially not notice the roadblock. Keep truck flashing lights on if manning roadblocks.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>				
ICS 204 - Assignment List			Updated 05/07/2018 17:28 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 35 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Security Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Additional Information			
If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221			
ICS 204 - Assignment List		Updated 05/07/2018 17:28 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 36 of 118	© TRG

ICS 204 - Assignment List			Task Force: Decon Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Decon Task Force Leader	Raiha, John	Husky Energy Inc.	218-390-4078	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Decon Task Force	Manpower: Responder	Manpower: Responder	4	
Decon Task Force	Miscellaneous	Decon Station	3	
Assignments				
<p>Conduct personnel decon for those exiting the hot zone or other designated area that requires Decon per standard procedure.</p> <p>Decon stations are at;</p> <ul style="list-style-type: none"> - #1 Cooling tower - West of flare - ALKY (Specifically for work inside ALKY unit, decontamination for ALKY chemical gear) <p>Asbestos decontamination facilities will be provided by the Asbestos contractor.</p>				
Communications				
Name / Function	Contact Details			
ERT Channel	8			
Channel 1 Talk Around	11			
Primary	1			
Secondary	2			
Radio	3 to 7			
Special Environmental Considerations				
<p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring. Any liquid hydrocarbon release shall be cleaned up immediately.</p>				
ICS 204 - Assignment List			Updated 05/07/2018 17:29 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 37 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Decon Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>Decon personnel must wear chemical gear over FR coveralls.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>Four station boot Decon:</p> <ol style="list-style-type: none"> 1. Simple Green and/or Orange Peel used to decon at Wash Station #1 2. Water rinse at station #2 3. Water rinse at station #3 4. Clean water tub at station #4 <p>Asbestos Decon will be overseen by asbestos removal contractors.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
<div></div>			
ICS 204 - Assignment List		Updated 05/07/2018 17:29 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 38 of 118	© TRG


ICS 204 - Assignment List			Other: Investigation Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Investigation Task Force	Shtand, Wally	Husky Energy Inc.	403 512-1437	
Investigation Task Force	Demchuk, Bill	Husky Energy Inc.	403 702-5724	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Investigation Task Force	Manpower: Responder	Manpower: Responder	18	
Assignments				
<p>Continue the DCS data replication:</p> <ul style="list-style-type: none"> - Yokogawa DCS - Net DAHS <p>Continue to support evidence collection as prioritized by operations.</p> <p>Baker Risk working on clearing asphalt removal on affected areas.</p> <p>Develop plan for walk down.</p> <p>Secure evidence storage:</p> <ul style="list-style-type: none"> - Confirm Location - Choose installation vendor 				
Special Site-Specific Safety Considerations				
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Be cognizant of the hazards of the product in reactor as well as nitrogen, fire and similar hazards.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>				
ICS 204 - Assignment List			Updated 05/10/2018 14:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 39 of 118	© TRG	

ICS 204 - Assignment List		Other: Investigation Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Additional Information			
If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221			
ICS 204 - Assignment List		Updated 05/10/2018 14:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 40 of 118	© TRG

ICS 204 - Assignment List			Task Force: Air Monitoring Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Environmental Monitoring Group Supervisor	Beattie, Dave	Husky Energy Inc.	218-348-9051	
Air Monitoring Task Force Leader	Armes, Will	GHD	519-497-8054	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Air Monitoring Task Force	Equipment: Air Monitoring	AreaRaes	32	
Air Monitoring Task Force	Equipment: Air Monitoring	MultiRaes	10	
Air Monitoring Task Force	Equipment: Air Monitoring	UltraRaes	10	
Air Monitoring Task Force	Equipment: Air Monitoring	Dust Track	10	
Air Monitoring Task Force	Manpower: Operator	Air Monitoring Supervisors	2	
Air Monitoring Task Force	Manpower: Responder	Industrial Hygienist	25	
Air Monitoring Task Force	Manpower: Responder	Asbestos Contractors	1	
Assignments				
<p>1. Continue to maintain a fixed perimeter air monitoring system that has been deployed to the area currently delineated as the hot zone. This monitoring will be conducted in accordance with the Site action levels described in the Air Monitoring Plan</p> <p>2. Continue to maintain a fixed perimeter air monitoring system that has deployed to the perimeter of the refinery process area at or near the fence line. This monitoring will be used to provide information regarding air quality in close proximity to potential sources of emissions of COI during the cleanup and recovery phases of the project.</p> <p>3. Mobile community monitoring teams will continue to conduct monitoring in the area outside the facility, with a focus on downwind monitoring, while the cleanup and recovery phases of the project are ongoing.</p> <p>4. Mobile on site teams will continue to conduct monitoring during De-Inventory activities.</p>				
Communications				
Name / Function		Contact Details		
ERT Channel		8		
Channel 1 Talk Around		11		
Primary		1		
Secondary		2		
Radio		3 to 7		
Special Environmental Considerations				
<p>Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p>				
ICS 204 - Assignment List			Updated 05/22/2018 10:16 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 41 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Air Monitoring Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>If working along the perimeter fence or other Husky property outside of refinery, contact security guards at 715-398-8220 to make them aware of your presence. Otherwise, the police will be called.</p> <p>When working along the refinery perimeter, be cognizant of slip, trip and fall hazards.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>When leaving vegetated areas outside of refinery, visually inspect clothing and skin for ticks.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
<div></div>			
ICS 204 - Assignment List		Updated 05/22/2018 10:16 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 42 of 118	© TRG

ICS 204 - Assignment List	Task Force: Air Monitoring Task Force
Incident Name: 2018 Superior Refinery Fire	Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]
20180521_Air Monitoring	



ICS 204 - Assignment List			Task Force: Water Sampling Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Environmental Monitoring Group Supervisor	Beattie, Dave	Husky Energy Inc.	218-348-9051	
Water Sampling Task Force Leader	Turner, Matt	Husky Energy Inc.	715-969-4873	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Water Sampling Task Force	Miscellaneous	Long-Handled Surface water Sampler	4	
Water Sampling Task Force	Miscellaneous	Lab Sample Containers	24	
Water Sampling Task Force	Miscellaneous	Water-Proof Shipping Containers	4	
Water Sampling Task Force	Manpower: Responder	Water Sampling Techs	3	
Assignments				
<p>Water sampling to be conducted once per week as directed by the Water Sampling Task Force Leader. When sampling occurs, the following will take place:</p> <ol style="list-style-type: none"> 1. Continue to collect water samples at designated sites utilizing appropriate water sampling equipment and techniques. 2. Sample at Four (4) pre-determined locations off site 3. Package and arrange water samples for delivery to selected labs for analysis. 4. Report findings to EUL and GHD. 5. Conduct on-site sampling for PFAS as needed. 				
Communications				
Name / Function		Contact Details		
ERT Channel		8		
Channel 1 Talk Around		11		
Primary		1		
Secondary		2		
Radio		3 to 7		
Special Environmental Considerations				
<p>Follow existing water sampling plan developed by GHD and approved by applicable agencies. All precautions should be taken to ensure proper sampling and handling. Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring. Any liquid hydrocarbon release shall be cleaned up immediately.</p>				
ICS 204 - Assignment List			Updated 05/22/2018 10:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 44 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Water Sampling Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>Please refer to GHD Health and Safety Plan for water sampling.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warrented, request lighth plants and other larger lighting.</p> <p>Life jackets are required when working over water. Life jackets are available in the Warehouse.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
ICS 204 - Assignment List		Updated 05/22/2018 10:17 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 45 of 118	© TRG



ICS 204 - Assignment List			Task Force: IH Monitoring Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Environmental Monitoring Group Supervisor	Beattie, Dave	Husky Energy Inc.	218-348-9051	
IH Monitoring Task Force Supervisor	Jones, Jacob			
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
IH Monitoring Task Force	Manpower: Responder	Industrial Hygienist	6	
IH Monitoring Task Force	Pumps	Sampling Pumps	5	
Assignments				
Continue asbestos monitoring on-site as directed by approved Asbestos Plan				
Personal monitoring for air contaminants. (VOC, Asbestos)				
Provide asbestos hazard support to ERT and on-site operations within the hot zone or other areas where insulation is damaged.				
Communications				
Name / Function		Contact Details		
ERT Channel		8		
Channel 1 Talk Around		11		
Primary		1		
Secondary		2		
Radio		3 to 7		
Special Environmental Considerations				
<p>Debris shall be assumed to be asbestos containing unless testing or other means of identification confirms otherwise. Actions shall be taken to minimize any release of presumed asbestos containing materials (PACM) to the environment. Any PACM disturbance/release/exposure shall be mitigated or cleaned up immediately and disposed of properly.</p> <p>Notification of any PACM activities shall be made to the GHD IH air monitoring group immediately for evaluation, mitigation and/or exclusion.</p>				
ICS 204 - Assignment List			Updated 05/07/2018 17:18 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 47 of 118	© TRG	

ICS 204 - Assignment List		Task Force: IH Monitoring Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>If working along the perimeter fence or other Husky property outside of refinery, contact security guards at 715-398-8220 to make them aware of your presence. Otherwise, the police will be called.</p> <p>When in the refinery, be cognizant of hazards associated with a fire zone.</p> <p>When working along the refinery perimeter, be cognizant of slip, trip and fall hazards.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
ICS 204 - Assignment List		Updated 05/07/2018 17:18 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 48 of 118	© TRG

ICS 204 - Assignment List			Task Force: Environmental Support Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Environmental Monitoring Group Supervisor	Beattie, Dave	Husky Energy Inc.	218-348-9051	
Environmental Support Task Force Leader	Turner, Matt	Husky Energy Inc.	715-969-4873	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Environmental Support Task Force	Manpower: Responder	Manpower: Responder	3	
Environmental Support Task Force	Boom	Boom	400	
Environmental Support Task Force	Sorbent: Boom	Sorbent: Boom	400	
Environmental Support Task Force	Vehicle	Vehicle	4	
Environmental Support Task Force	Vacuum Truck	Vacuum Truck	1	
Environmental Support Task Force	Manpower: Operator	Vac Truck Operators	2	
Environmental Support Task Force	Manpower: Operator	Operator	1	
Environmental Support Task Force	Excavator	Mini Excavator	1	
Assignments				
<p>Boom Maintenance:</p> <p>The team will travel to the current boom sites along Newton Creek to assess the condition of the boom. The morning crew will replace all absorbent boom that appears to have petroleum contamination. Any containment boom that is compromised will be put into 55 gallon steel drums that are labeled with a non-hazardous waste label filled in with "Oily Absorbent Booms". Full drums will be brought to the 90 day storage building. Pictures of each boom site should be taken both before and after any upkeep for documentation. Report to acting shift foreman for any additional work he may have for them.</p> <p>Respond to any immediate actions, environmental concerns. (ie: Cleanup of contaminants at boom locations, address contamination issues at stinson avenue) as directed by Environmental Support Task Force Leader.</p>				
Communications				
Name / Function		Contact Details		
Primary		1		
Secondary		2		
Radio		3 to 7		
ERT Channel		8		
Channel 1 Talk Around		11		
Channel 2 Talk Around		12		
Special Equipment / Supplies Needed for Assignment				
Steel Drums, wheelbarrow				
Special Environmental Considerations				
<p>Presence of sheen/oil at any location shall be relayed to the boom maintenance task force leader. Actions shall be taken to minimize any release of hydrocarbons to the environment. Any liquid hydrocarbon release shall be cleaned up immediately and disposed of properly.</p> <p>Notification of any venting/release of vapor/liquid hydrocarbon shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p>				
ICS 204 - Assignment List			Prepared By Planning, Updated 05/07/2018 17:20 UTC -6:00 PP	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 49 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Environmental Support Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Be aware of slipping hazards on sides of banks of creek and other areas.</p> <p>When work involves roadways, utilize Hi Viz vest.</p> <p>Wear a life jacket when working in areas of deeper water. Consider slipping hazards and what might happen if you were to slip into creek while deploying boom or into pond while sampling.</p> <p>Be cognizant of the products being handled.</p> <p>Utilize proper lifting techniques and utilize mechanical lifting techniques on heavy boom or other objects.</p> <p>Inspect for ticks when traveling in grassy or wooded areas.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
ICS 204 - Assignment List		Prepared By Planning, Updated 05/07/2018 17:20 UTC -6:00 PP	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 50 of 118	© TRG

Asphalt Recovery and Boom Management Plan

Crew: 2 shifts, 2 workers each shift. Workers must have current HAZWOPER Training

Frequency: Twice per day (once per shift) for a week

Materials: Containment Boom (100ft)
Absorbent Boom (100ft)
55 gallon steel drums (4)
Non-Hazardous Waste Labels (4)
Shovels (2)
Wheelbarrow (1)
Pickup Truck (1)
Boom Location Map (1)
High Visibility Vest for Worker (2)

Objective: **Stinson Ave Ditch Asphalt Recovery:** Teams of two with current HAZWOPER training will travel along the northern side of Stinson Ave and collect any asphalt present. Asphalt may appear in “globs” with sizes ranging from a softball to a pea. Collected asphalt can be placed in a wheelbarrow while traversing Stinson Ave and ultimately transferred into 55 gallon steel drums. The drums are to be labeled with a non-hazardous waste sticker that is filled in with “Asphalt + Soil”. Under no circumstances should any other material be collected as to not interfere with the incident investigation. Full drums will be brought to the 90 day storage building and properly stored. Pictures of gross asphalt contamination should be taken for documentation purposes.

Newton Creek Boom Maintenance: After conducting the asphalt recovery portion of the plan, the same team of two will travel to the current boom sites along Newton Creek to assess the condition of the booms. The morning crew will replace all the absorbent boom in the creek. The afternoon crew will replace any absorbent boom that appears to have petroleum contamination. Any containment boom that is compromised should be replaced or adjusted to ensure functionality. Spent absorbent booms will be put into 55 gallon steel drums that are labeled with a non-hazardous waste label that is filled in with “Oily Absorbent Booms”. Full drums will be brought to the 90 day storage building and properly stored. Pictures of each boom site should be taken both before and after any upkeep for documentation purposes.

After Both Tasks Are Complete: Once the tasks have been completed, the team will then contact the acting shift foreman for any additional work he may have for them.

ICS 204 - Assignment List			Task Force: Wildlife Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Environmental Monitoring Group Supervisor	Beattie, Dave	Husky Energy Inc.	218-348-9051	
Wildlife Task Force Leader	Battaglia, Chris	Focus Wildlife	310-386-5965	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Wildlife Task Force	Manpower: Responder	Manpower: Responder	3	
Assignments				
<p>Minimize access to asphalt tank farm by installing fencing (chain link & silt fence), continue to clean up and maintain pennant & mylar flagging around all of the asphalt and 6 oil containment area.</p> <p>Implement Canadian goose nest and egg depredation as defined in the wildlife plan.</p> <p>Implement active wildlife hazing as appropriate.</p> <p>Continuous active monitoring of wildlife on-site and off-site around the facility</p> <p>All operations should be in accordance with the approved Wildlife Plan.</p> <p>Active wildlife rehabilitation.</p> <p>Removing oil in concrete ditch and installing snow fence along the ditch.</p>				
Special Equipment / Supplies Needed for Assignment				
100yd sand Pre-sectioned mobile fencing PFD Flagging material				
Special Environmental Considerations				
Follow existing wildlife management plan and approved by applicable agencies. Actions shall be taken to minimize any impact to wildlife. Notification to the Wildlife Group and Environmental Unit Leader of any identified impacts to wildlife (terrestrial, aquatic, avian). Additionally, notification of any hydrocarbon release shall be made to the GHD air monitoring group immediately for consideration in air monitoring.				
<div> <div>ICS 204 - Assignment List</div> <div>Updated 05/07/2018 17:22 UTC -6:00</div> </div> <div> <div>INCIDENT ACTION PLAN SOFTWARE™</div> <div>Printed 05/22/2018 17:18 UTC -6:00</div> </div> <div> <div>Page 52 of 118</div> <div>© TRG</div> </div>				

ICS 204 - Assignment List		Task Force: Wildlife Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Be cognizant of the hazards of the products being handled.</p> <p>If working along the perimeter fence or other Husky property outside of refinery, contact security guards at 715-398-8220 to make them aware of your presence. Otherwise, the police will be called.</p> <p>When working along the refinery perimeter, be cognizant of slip, trip and fall hazards.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p> <p>Be sure to wear a life jacket when working over water. Life jackets are available in the Warehouse.</p> <p>Inspect for ticks when traveling in grassy or wooded areas.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
<div></div>			
ICS 204 - Assignment List		Updated 05/07/2018 17:22 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 53 of 118	© TRG

ICS 204 - Assignment List			Task Force: Waste Management Task Force	
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Operations Personnel				
Position	Name	Affiliation	Contact Number(s)	Work Shift
Operations Section Chief	Fredman, Peter	Husky Energy Inc.	320-288-6161	
Deputy Operations Section Chief	Schade, Kollin	Husky Energy Inc.	317-292-6594	
Environmental Monitoring Group Supervisor	Beattie, Dave	Husky Energy Inc.	218-348-9051	
Waste Management Task Force Leader	Turner, Matt	Husky Energy Inc.	715-969-4873	
Resources Required				
Area Of Operation	Resource Kind	Description	Quantity	Size
Waste Management Task Force	Manpower: Responder	Manpower: Responder	2	
Waste Management Task Force	Manpower: Operator	Operator	1	
Waste Management Task Force	Front-end loader	Front-end loader	1	
Assignments				
<p>Contingent on Baker Risk clearance on a per site basis:</p> <p>Dispose of asphalt removed by the Asphalt Removal Task Force.</p> <p>Movement of disposal equipment should be directed by Asphalt Removal Task Force Leader</p> <p>All operations to follow the approved Asbestos and Waste Management Plans.</p>				
Special Environmental Considerations				
<p>Follow existing waste management plan and approved by applicable agencies. Actions shall be taken to minimize any release of hydrocarbons to the environment. Any hydrocarbon release shall be cleaned up immediately and disposed of properly. Notification of any hydrocarbon release shall be made to the GHD air monitoring group immediately for consideration in air monitoring.</p>				
<div> <div>ICS 204 - Assignment List</div> <div>Updated 05/07/2018 17:23 UTC -6:00</div> </div>				
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 54 of 118	© TRG	

ICS 204 - Assignment List		Task Force: Waste Management Task Force	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
Special Site-Specific Safety Considerations			
<p>If working in Hot or Warm Zone, must follow entry procedures.</p> <p>Minimum PPE for work in refinery is full FR clothing, Hard Hat, Safety Glasses with side shields and safety boots. Additional PPE may be required depending on work to be performed or areas to be entered. Refer to Safe Work Permit and Safe Work Permit writers for further guidance.</p> <p>A Safe Work Permit is required for all work. Safe Work Permits can be obtained from operators in the ERT Building.</p> <p>Hazard assessment must be done to plan safe work.</p> <p>Be cognizant of the hazards of the products being handled.</p> <p>Use flashlights, vehicle lights and other lighting during nighttime activities. If warranted, request light plants and other larger lighting.</p> <p>For work in asbestos (asbestos danger tape) areas of the hot zone or where damage has occurred to insulation or equipment outside of hot zone, area must be assessed for asbestos and other hazardous materials by an Industrial Hygienist from GHD. If concerns are found, GHD will work with asbestos removers to render the area safe for work if possible. Any concerns found as part of this assessment must be addressed prior to any work being done.</p> <p>The Plant Emergency Alarm system will signal need to evacuate from the site. The plant radio system will be used to signal an evacuation if the primary should fail.</p> <p>Be aware of the potential for severe weather. In the refinery, the Shift Foreman will make an announcement on the plant radio system if there are special precautions or if there is a need to take shelter.</p>			
Additional Information			
<p>If impacted wildlife are observed. Do not approach or attempt to capture. Please contact Husky Hill Avenue guard shack at 715-398-8220 or 221</p>			
<div></div>			
ICS 204 - Assignment List		Updated 05/07/2018 17:23 UTC -6:00	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:18 UTC -6:00	Page 55 of 118	© TRG

ICS 205 - Radio Communications					Version Name: Overall				
Incident Name: 2018 Superior Refinery Fire					Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]				
Radio Channel Information									
Ch #	Function	Channel Name/ Trunked Radio System Talkgroup	Assignment	Rx Freq N or W	Rx Tone/NAC	Tx Freq N or W	Tx Tone/NAC	Mode (A, D, or M)	Remarks
1	Primary	Primary Radio Channel - Repeated							
2	Secondary	Secondary Radio Channel - Repeated							Secondary Repeated Channel Unit and Uses
3 to 7	Radio	Radio to Radio Channels							Working Channel
8	ERT Channel	Emergency Response Channel							Emergency Response Team Channel
11	Channel 1 Talk Around	Channel 1 Talk Around							Use this channel in case of failure of repeated Channel 1
12	Channel 2 Talk Around	Channel 2 Talk Around							Use this channel in case of failure of repeated Channel 2
Special Radio Instructions									
ICS 205 - Radio Communications					Prepared By Logistics, Updated 05/10/2018 13:14 UTC -6:00 PP				
INCIDENT ACTION PLAN SOFTWARE™			Printed 05/22/2018 17:19 UTC -6:00		Page 56 of 118			© TRG	

ICS 205a - Communications List			Version Name: Overall		
Incident Name: 2018 Superior Refinery Fire			Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]		
Local Communications Information					
Name	Incident Assigned Position	Mobile Phone	Work Phone	Email	Notes
Goedde, Ed	Incident Commander	Non-Responsive		ed.goedde@huskyenergy.com	
Williams, Blake	Deputy Incident Commander		403 298-7443	blake.williams@huskyenergy.com	
Morrison, Dave	Agency Representative			morrison.david@epa.gov	
Gabert, Jeff	Public Information Officer				
Sheedy, Colin	Liaison Officer		403-298-6794	colin.a.sheedy@huskyenergy.com	
O'Brien, John	Safety Officer				
Syphard, Dan	Legal Officer				
Fredman, Peter	Operations Section Chief			peter.fredman@huskyenergy.com	
Schade, Kollin	Deputy Operations Section Chief				
Tokarz, Christina	Planning Section Chief			Christina.Tokarz@huskyenergy.com	
Choate, Jerry	Logistics Section Chief			jerry.choate@huskyenergy.com	
Oestreich, Scott (5/21)	Deputy Logistics Section Chief				
Oestreich, Scott	Deputy Logistics Section Chief (5/21)				
Kowitz, Kim	Finance Section Chief				
Verrill, John	Deputy Finance Section Chief				
Broadbent, Evan	Resource Unit Leader			ebroadbent@responsegroupinc.com	
Takahashi, Yoshimi	Documentation Unit Leader			Yoshimi.takahashi@huskyenergy.com	
Cooke, Lorelee	Documentation Unit Leader		403 298-6238	lorelee.cooke@huskyenergy.com	
Beattie, Dave	Environmental Unit Leader			dave.beattie@huskyenergy.com	
Gavalas, Judith	HR Officer				
Bachhuber, Julie	HR Officer			julie.bachhuber@huskyenergy.com	
Lozada, Rene	ICS Process Advisor		832-763-8541	rlozada@responsegroupinc.com	
Hill, Travis	GIS Specialist			thill@responsegroupinc.com	
Black, Jason	Supply Unit Leader		jason.black@huskyenergy.com		
Bruckelmyer, Jason	Support Branch Director				
ICS 205a - Communications List			Prepared By Logistics, Updated 05/20/2018 08:53 UTC -6:00 PP		
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:19 UTC -6:00		Page 57 of 118		© TRG

ICS 206 - Medical Plan				Version Name: Overall				
Incident Name: 2018 Superior Refinery Fire				Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]				
Medical Aid Stations								
<i>Name</i>	<i>Location</i>	<i>Paramedic On Site</i>	<i>Phone</i>	<i>Radio</i>				
Superior Refinery Medical Aid Station	-92.07578 46.68889	<input checked="" type="checkbox"/>						
Transportation (Ground and/or Air Ambulance Services)								
<i>Ambulance Service</i>	<i>Location</i>	<i>Phone</i>	<i>Radio</i>	<i>Air</i>	<i>ALS</i>			
Global Air Ambulance	3500 Tower Ave. Superior, WI 54888 -92.07202 46.68952	Ph1: (305) 514-0942		<input checked="" type="checkbox"/>	<input type="checkbox"/>			
Gold Cross Ambulance Service	4505 W. Michigan St. Duluth, MN -92.15475 46.74444	Ph1: (218) 628-9323		<input type="checkbox"/>	<input type="checkbox"/>			
Hospitals								
<i>Hospital</i>	<i>Location</i>	<i>Phone</i>	<i>Radio</i>	<i>Air Travel Time</i>	<i>Ground Travel Time</i>	<i>Trauma Center</i>	<i>Helipad</i>	<i>Burn Center</i>
Essentia Health St. Mary's Hospital	3500 Tower Ave Superior, MN -92.10236 46.69748	Ph1: (715) 817-7000		min	15 min	II	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Essentia Health Duluth (Miller Dwan) Thermal or Chemical Burns	502 E 2nd St Duluth, MN -92.09367 46.79244	Ph1: (218) 727-8762		min	30 min	II	<input type="checkbox"/>	<input checked="" type="checkbox"/>
St Luke's Duluth	915 East First Street Duluth, MN -92.08762 46.79718	Ph1: (218) 249-5555		min	30 min	II	<input checked="" type="checkbox"/>	<input type="checkbox"/>
				min	min		<input type="checkbox"/>	<input type="checkbox"/>
ICS 206 - Medical Plan				Prepared By Medical, Updated 05/01/2018 13:08 UTC -6:00 PP				
INCIDENT ACTION PLAN SOFTWARE™		Printed 05/22/2018 17:19 UTC -6:00		Page 58 of 118		© TRG		

ICS 206 - Medical Plan		Version Name: Overall	
Incident Name: 2018 Superior Refinery Fire		Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]	
<p align="center">Special Medical Emergency Procedures</p>			
<p>All injured employees who require more than in-house first aid, (i.e. lacerations requiring stitches, severe eye problems, severe strains/sprains or fractures) will be sent to the following medical facility:</p> <p>Essentia St. Mary's Occupational Medicine Clinic 3500 Tower Ave Superior, WI (715) 817-7100</p>			
<p>INJURIES INVOLVING EXPOSURE TO HYDROFLUORIC ACID</p> <p>For minor exposures, the employee may be transported to Essentia St. Mary's Emergency Room in Superior, the Essentia Duluth Clinic Occupational Medicine Clinic or the Essentia St. Mary's Hospital Emergency Room in Duluth.</p> <p>For all but minor exposures, the employee should be transported by ambulance to: St. Mary's Hospital Emergency Room in Duluth: 407 East 3rd Street Duluth. MN 218-786-4000</p>			
<p>INJURIES INVOLVING THERMAL OR CHEMICAL BURNS</p> <p>For injuries involving all but minor thermal or chemical burns, employees should be transported by ambulance to: Essentia Miller-Dwan Burn Center 502 E. Second St., First Floor Duluth, MN (218) 786-2815</p>			
<div></div>			
ICS 206 - Medical Plan		Prepared By Medical, Updated 05/01/2018 13:08 UTC -6:00 PP	
INCIDENT ACTION PLAN SOFTWARE™	Printed 05/22/2018 17:19 UTC -6:00	Page 59 of 118	© TRG

MEDICAL SERVICES/EMPLOYEE MEDICAL RECORDS/ WORKER'S COMPENSATION

SCOPE

This Standard Practice Instructions is to be considered Husky Superior company policy and minimum acceptable standards under normal conditions. Stricter requirements may apply under certain situations. If a problem is encountered, consultation with a safety professional should be considered before proceeding. Keep in mind that any alternative procedure must be at least as effective as these instructions in providing a safe workplace.

RATIONALE

This procedure was developed to inform all supervisors of the steps which need to be taken to insure that all injured employees are properly cared for, to explain access to employee medical records, and to explain the worker's compensation procedure.

APPLICATION

This policy describes the procedure that needs to be followed by all Husky Superior employees when it is necessary to obtain medical services, access medical records, or receive worker's compensation.

DEFINITIONS

Minor injury – Any injury that can be properly attended with in-house first aid. This type of injury might include strains/sprains, lacerations not requiring stitches, irrigating eyes or minor burns (either chemical or thermal).

Medical First-Aid Injuries – Any injury that can be properly attended by a physician with first-aid treatment.

Serious Injury – An injury that resulted in an OSHA recordable injury, lost-time injury (either lost workdays or restricted workdays) or fatality.

PROCEDURE FOR OBTAINING MEDICAL SERVICES

Note: On-Shift Emergency Response Team (ERT) Members should be called to assist on all, but very minor, medical incidents.

DAYTIME HOURS, MONDAY THROUGH FRIDAY

All injured employees who require more than in-house first aid, (i.e. lacerations requiring stitches, severe eye problems, severe strains/sprains or fractures) will be sent to the following medical facility:

Essentia SMDC Occupational Medicine Clinic
Duluth Clinic 3rd Street Building
400 E. Third St.
Duluth, MN
(218) 786-3392

-or-

Essentia St. Mary's Occupational Medicine Clinic
3500 Tower Ave
Superior, WI
(715) 817-7100

- A. The immediate supervisor shall contact the Safety Department and advise of the injured employee.
- B. The Safety Manager or other member of the Safety Department will notify Essentia that an employee of Husky Superior is in route and give them a brief description of the employee's condition.
 - a. If requested by the Employee's Supervisor, the medical facility will also be advised that a drug screen and breath alcohol test according to the Husky Superior Drug and Alcohol Program will be needed.
- C. The Safety Manager, other member of the Safety Department or the Shift Foreman/Employee's Supervisor should accompany the injured employee to the medical facility to assure prompt and immediate medical attention is obtained. The medical facility will direct proper medical attention/treatment.

EVENINGS, WEEKENDS, HOLIDAYS

If an employee is injured Monday through Friday, after 5:00 PM, on a Saturday, Sunday, or holiday, the shift supervisor will follow these guidelines.

Minor Injuries

All injured employees who require more than in-house first aid, (i.e. lacerations requiring stitches, severe eye problems, severe strains/sprains or fractures) will be sent to the following medical facility:

Essentia St. Mary's Emergency Room
3500 Tower Ave
Superior, WI 54880
Phone: (715) 817-7100

Serious Injury

Some injuries may be such that immediate outside medical attention is required. If it has been determined that the injury is not life threatening but will require outside medical attention, the injured employee should be transported either by company vehicle or by ambulance. Unless directed by ambulance or other emergency responders, the employee should be transported to the Emergency Room at Essentia St. Mary's Superior or Duluth.

- A. The immediate supervisor shall contact the Safety Department and advise of the injured employee.
- B. The Supervisor or the Safety Manager will notify Essentia that an employee of Husky Superior is in route and give them a brief description of the employee's condition.
 - a. If requested by the Employee's Supervisor, the medical facility will also be advised that a drug screen and breath alcohol test according to the Husky Superior Drug and Alcohol Program will be needed.
- C. The Shift Foreman/Employee's Supervisor, Safety Manager/Safety Department Member or other Husky Superior Employee should accompany the injured employee to the medical facility to assure prompt and immediate medical attention is obtained. The medical facility will direct proper medical attention/treatment.

LIFE THREATENING EMERGENCIES

If the injury is life threatening, the injured employee will be transported to the hospital by ambulance. An injured employee under these conditions will not be transported by a Husky Superior or contractor employee. The supervisor in charge shall call or designate someone to call 911.

Examples of Life Threatening Situations

- a. Employee is unconscious
- b. Severe bleeding
- c. Cyanosis (blue lips, fingernails)
- d. Severe head injury
- e. Severe chest pain, pain radiating down arms
- f. Compound fractures (bones exposed)
- g. Immediate excessive swelling
- h. Hypothermia
- i. Heatstroke
- j. Stroke

Information for Operator at 911

- a. Give a brief description of the problem. This will enable EMT's to prepare the equipment necessary for the immediate care of the injured employee.
- b. Give direction to the appropriate gate nearest the accident; advise that there will be someone at the gate to escort the emergency vehicle to the site of the accident.

After the 911 call, contact the following:

- a. Call security and advise them of the pending arrival of the emergency vehicle.
- b. Call the Essentia Medical facility that the employee was transported too and advise them that an employee of Husky Superior is in route and give them a brief description of the employee's condition and require a post accident drug/alcohol screen.
- c. Notify either the Safety Manager, on-call personnel (weekends/holidays), or any available member of management.

INJURIES INVOLVING EXPOSURE TO HYDROFLUORIC ACID

For minor exposures, the employee may be transported to Essentia St. Mary's Emergency Room in Superior, the Essentia Duluth Clinic Occupational Medicine Clinic or the Essentia St. Mary's Hospital Emergency Room in Duluth.

For all but minor exposures, the employee should be transported by ambulance to:

St. Mary's Hospital Emergency Room in Duluth:
407 East 3rd Street
Duluth, MN
218-786-4000

Follow notification and other procedures as outlined above depending on the time of day that the exposure occurs.

INJURIES INVOLVING THERMAL OR CHEMICAL BURNS

For injuries involving all but minor thermal or chemical burns, employees should be transported by ambulance to:

Essentia Miller-Dwan Burn Center
502 E. Second St., First Floor
Duluth, MN
(218) 786-2815

Follow notification and other procedures as outlined above depending on the time of day that the exposure occurs.

SUPERVISOR'S INCIDENT/INJURY REPORT

The immediate supervisor shall complete the Supervisor's Incident/Injury Report form as soon as possible after the occurrence, but no later than the end of the shift on which it occurred.

NOTE: Husky Superior is required to notify OSHA within 8-hours of any incident that results in a fatality or the hospitalization of three or more employees. This notification will result in an OSHA investigation of the incident.

ACCESS TO RECORDS

The following records shall be made available, upon request, to any employee and to their representatives for examination and copying at a reasonable time and manner:

- a. OSHA 300 log;
- b. Work Comp First Report of Injury;
- c. OSHA 300A Annual Summary of occupational injuries and illnesses;
- d. Pulmonary function and audiometric testing.
- e. Industrial hygiene sampling records.

Medical records are kept in a confidential file, separate from the personnel file in the general administrative office. These files include the pre-placement physical record and worker's compensation information. Audio and pulmonary medical records are maintained in a separate file in the Safety Department. Employees may inspect their medical records by contacting the Supervisor of Administrative Services.

WORKER'S COMPENSATION

An employee involved in a personal injury has the responsibility to perform the following steps:

1. Receive medical attention if needed.
2. Report injury to supervision immediately!
3. Complete all appropriate forms with supervision.

NOTE: These forms must be completed as soon as possible after the occurrence, but no later than at the end of the shift on which it occurred.

4. Participate in all investigations as necessary.

If an employee has an injury or illness that has not been reported as an accident but the employee believes it is work related, the employee must inform the company of the circumstance of the injury or illness and how it relates to the work place.

When the employee gives notice of an injury, the employee may see a physician of his/her choice. However, Husky Superior reserves the right to send the employee to another doctor for a second opinion at its discretion. In emergencies, Husky Superior may choose the practitioner without offering a choice, but after the emergency, the employee still has the option of seeing his/her own physician. The employee also may change practitioners once, with notice to Husky Superior.

The employee must provide Husky Superior with a doctor's report that provides evidence that the illness/injury is related to the employee workplace.

Clinic/Hospital Information

Minor Injuries - Daytime Hours, Monday through Friday (either):

Essentia SMDC Occupational Medicine Clinic
Duluth Clinic 3rd Street Building
400 E. Third St.
Duluth, MN
(218) 786-3392

Essentia St. Mary's Occupational Medicine Clinic
3500 Tower Ave
Superior, WI
(715) 817-7100

Minor Injuries - Evenings, Weekends or Holidays:

Essentia St. Mary's ER - Superior
3500 Tower Ave
Superior, WI 54880
(715) 817-7100

Serious Injuries

Unless directed by ambulance or other emergency responders, the employee should be transported to either:

Essentia St. Mary's ER - Superior
3500 Tower Ave
Superior, WI 54880
(715) 817-7100

Essential St. Mary's Hospital ER - Duluth:
407 East 3rd Street
Duluth, MN
218-786-4000

HF Minor Exposures (any of the following):

Essentia St. Mary's ER - Superior
3500 Tower Ave
Superior, WI 54880
(715) 817-7100

Essentia Occup. Medicine Clinic
Duluth Clinic - 3rd Street Building
400 E. Third St.
Duluth, MN
(218) 786-3392


Essential St. Mary's ER - Duluth:
407 East 3rd Street
Duluth, MN
218-786-4000

HF Serious Exposures:

Essential St. Mary's Hospital ER - Duluth:
407 East 3rd Street
Duluth, MN
218-786-4000

Serious Thermal or Chemical Burns

Essentia Miller-Dwan Burn Center
502 E. Second Street, First Floor
Duluth, MN
(218) 786-2815



ICS 207 - Organization Chart


Version Name: Period 11 - Operations

Incident Name: 2018 Superior Refinery Fire

Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]

Operations Section Chief
Fredman, Peter

Deputy Operations Section Chief
Schade, Kollin



ICS 208 - Site Safety Plan					Version Name: Refinery Site				
Incident Name: 2018 Superior Refinery Fire					Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]				
Applies to Site: Superior Refinery									
Site Characterization									
Water		Land		Weather		Partly Cloudy			
Wave Height		Land Use		Air Temp		23.6 Fahrenheit			
Speed				Wind Speed		9			
Direction				Direction		SSW			
Site Hazards									
Yes	No	Hazards	Yes	No	Hazards	Yes	No	Hazards	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Boat Safety	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Fire, Explosion, In-situ Burning	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Pump Hose	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Chemical Hazards	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Heat Stress	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Slips, Trips, and Falls	
<input type="checkbox"/>	<input checked="" type="checkbox"/>	Cold Stress	<input type="checkbox"/>	<input type="checkbox"/>	Helicopter Operations	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Steam and Hot Water	
<input type="checkbox"/>	<input type="checkbox"/>	Confined Spaces	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Lifting	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Trenching/Excavation	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Drum Handling	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Motor Vehicles	<input type="checkbox"/>	<input checked="" type="checkbox"/>	UV Radiation	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Equipment Operations	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Noise	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Visibility	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Electrical Operations	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Overhead/Buried Utilities	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Weather	
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Fatigue	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Plants/Wildlife	<input checked="" type="checkbox"/>	<input type="checkbox"/>	Work Near Water	
Air Monitoring Limits									
Oxygen Level		19.5 to 22.5%	Benzene		1 PPM	Carbon Moxide		35 PPM	
LEL		5%	Total Hydrocarbons		500 PPM	Hydroflouric Acid		3 PPM	
Hydrogen Sulfide		10 PPM	Asbestos		0.1 Fiber per cc	Sulfur Dioxide		2 PPM	
Engineering Controls									
<input type="checkbox"/>	Source of release secured		<input type="checkbox"/>	Valve(s) closed		<input checked="" type="checkbox"/>	Energy sources locked/tagged out		
<input checked="" type="checkbox"/>	Site secured		<input checked="" type="checkbox"/>	Facility shut down					
Personal Protective Equipment Required									
<input type="checkbox"/>	Impervious suit		<input checked="" type="checkbox"/>	Hard hats		<input checked="" type="checkbox"/>	Boots		
<input type="checkbox"/>	Inner gloves		<input checked="" type="checkbox"/>	Respirators		<input checked="" type="checkbox"/>	Bunker Gear		
<input checked="" type="checkbox"/>	Outer gloves		<input checked="" type="checkbox"/>	Eye protection		<input checked="" type="checkbox"/>	ERT SCBA		
<input checked="" type="checkbox"/>	Flame resistant clothing		<input checked="" type="checkbox"/>	Personal flotation					
Additional Control Measures Established									
<input checked="" type="checkbox"/>	Decontamination		<input checked="" type="checkbox"/>	Illumination		<input checked="" type="checkbox"/>	Additional stations established		
<input checked="" type="checkbox"/>	Sanitation		<input type="checkbox"/>	Medical surveillance		<input type="checkbox"/>	Facilities provided		
Work Plan									
<input checked="" type="checkbox"/>	Booming		<input type="checkbox"/>	Excavation		<input type="checkbox"/>	Hot work		
<input type="checkbox"/>	Skimming		<input checked="" type="checkbox"/>	Heavy equipment		<input checked="" type="checkbox"/>	Appropriate permits used		
<input checked="" type="checkbox"/>	Vac trucks		<input checked="" type="checkbox"/>	Sorbent pads					
<input checked="" type="checkbox"/>	Pumping		<input checked="" type="checkbox"/>	Patching					
Training									
<input checked="" type="checkbox"/>	Verified site workers trained per local/federal regulatory requirements			Training Requirements					
ICS 208 - Site Safety Plan					Prepared By O'Brien, John, Updated 05/22/2018 13:47 UTC -6:00 PP				
INCIDENT ACTION PLAN SOFTWARE™		Printed 05/22/2018 17:19 UTC -6:00			Page 68 of 118			© TRG	

ICS 208 - Site Safety Plan				Version Name: Refinery Site			
Incident Name: 2018 Superior Refinery Fire				Period: Period 11 [05/23/2018 06:00 - 05/30/2018 06:00]			
Organization							
Position		Name	Telephone/Radio	Position		Telephone/Radio	
Incident Commander		Long, David	403-542-1338	Safety Officer		218-390-4367	
Deputy Incident Commander		Harris, Paul	780 522-5060	Operations Section Chief		320-288-6161	
Emergency Plan							
<input checked="" type="checkbox"/>	Fire Prevention Plan		<input checked="" type="checkbox"/>	Evacuation Plan			
<input checked="" type="checkbox"/>	Alarm System		<input checked="" type="checkbox"/>	First Aid Location			
Notifications							
Facility			Phone	Facility		Phone	
<input checked="" type="checkbox"/>	Hospital	Essential St. Mary's Hospital	218-786-4000	<input checked="" type="checkbox"/>	Fire	Superior Fire Department	
<input checked="" type="checkbox"/>	Ambulance	Gold Cross	911	<input checked="" type="checkbox"/>	Law Enforcement	Superior Police Department	
<input type="checkbox"/>	Air Ambulance			<input checked="" type="checkbox"/>	Emergency Response/Rescue	Plant Radio Channel 1	
Initial Briefing							
<input type="checkbox"/>	Initial safety briefing prepared for each site						
Attachments/Appendices							
Attachment			Filename				
SDSs are available on the Refinery Intranet..rtf			SDSs are available on the Refinery Intranet..rtf				
ICS 208 - Site Safety Plan				Prepared By O'Brien, John, Updated 05/22/2018 13:47 UTC -6:00 PP			
INCIDENT ACTION PLAN SOFTWARE™		Printed 05/22/2018 17:19 UTC -6:00		Page 69 of 118		© TRG	

SDSs are available on the Refinery Intranet.

Contact a member of the Refinery Safety Department if you have questions.

Superior Refinery Fire

Main Column Ovhd Receiver De-Inventory Plan

Authored by: Aaron Laszewski

Date: 5/18/18

Approved by:

Operations Section Chief: Peter Z

Environmental Unit Leader: [Signature]

Safety Officer: [Signature]

Planning Section Chief: [Signature]

Investigation Task Force Leader: [Signature]

Incident Commander: [Signature]

Prepared by Operations Section

SEE BACK


* BEGIN DE-INVENTORY IDENTIFICATION BY PIPING LINE.




Asbestos Remediation Plan

2018 Superior Refinery Fire

Superior Refining Company LLC
Husky Superior Refinery, Superior, Wisconsin


Matthew G. Lazaric
(Wisconsin Asbestos License All-13341)


David Keller, CIH, CSP

Operations Section Chief	 Signature	5/4/18 Date
Planning Section Chief	 Signature	4 MAY 18 Date
Incident commander	 Signature	5/4/18 Date



Table of Contents

1.	Introduction and Objectives	1
2.	Exposure Standards and Guidelines	2
2.1	Perimeter Exposure Monitoring Criteria	2
3.	Quality Assurance/Quality Control (QA/QC) and Reporting	3
4.	Asbestos Abatement / Cleanup Plan	4
4.1	Offsite / Extra-refinery Cleanup	4
4.2	Small-Scale, Short Term Abatement.....	4
4.3	General Asbestos Abatement and Site Cleanup	5



1. Introduction and Objectives

At the request of Superior Refining Company LLC (SRC), a subsidiary of Husky Energy, Inc. (Husky), GHD Services Inc. (GHD) will provide air monitoring and industrial hygiene (IH) support related to the 2018 Superior Refinery fire. The incident occurred at the SRC refinery (Site) located in Superior, Wisconsin. These services are provided to assist SRC with ensuring health and safety during cleanup and management of asbestos-containing materials or suspected asbestos-containing materials (collectively, ACM) that may be encountered during the incident and subsequent response and remediation efforts.

The purpose of this work plan is to implement a systematic assessment and recovery effort. This plan addresses proper ACM management during the response and remediation phases of the project. The specific objectives include the following:

- Prevent public or site worker exposure to ACM;
- Sample and document potential airborne asbestos exposures at the site perimeter during active asbestos cleanup / abatement;
- Identify and recover ACM external to the refinery fence line;
- Identify and recover damaged ACM within plant affected by the incident;
- Periodically observe cleanup activities to ensure proper cleanup and waste packaging methods are being utilized. Observe employee and equipment decontamination procedures; and
- Where safe and appropriate, sample materials suspected to contain asbestos. At this time, bulk sample collection is anticipated to be limited to sampling insulation that is remaining on fixed plant equipment including exchangers, drums, etc., that may be damaged and may require removal or repairs as overall plant repairs are conducted.

To accomplish the objectives outlined above, we propose the following activities:

- Ambient Air Sampling plan:
 - a. During asbestos abatement monitoring, air samples will be collected along the perimeter of the asbestos abatement exclusion zone.
 - b. The site asbestos abatement contractor (In-Line Construction or other Wisconsin-licensed asbestos abatement contractor) will collect personal samples from their employees that are performing abatement. GHD will receive and review all personal sample results.
 - c. As appropriate, collect ongoing area samples surrounding the refinery.
 - d. Analysis of air samples will be performed using phase contrast microscopy (PCM) with transmission electron microscopy (TEM) to be used as needed to clarify results.
- ACM Debris Survey
 - a. As access is available to interior portions of the plant, identify locations for and coordinate placing asbestos warning / danger tape around locations of potential asbestos.
 - b. Perform a limited visual asbestos survey of the fire affected and other damaged areas to determine areas that have ACM debris.
 - c. Mark areas that have visible ACM debris.



- Damaged ACM Survey
 - a. Where safe to do so, perform an asbestos survey of the fire affected and other damaged areas to determine equipment, piping, etc. that have ACM debris.
 - b. As appropriate, collect bulk samples of suspect materials to confirm asbestos content so that the materials can be properly managed during the recovery.
 - c. Mark on drawings, equipment, piping, etc. that has damaged ACM debris

GHD will continue air monitoring services until the project is completed and potential worker or community exposures to airborne asbestos fibers associated with the incident are eliminated or until directed by Husky that this service should be demobilized. The air monitoring data will be collected and compiled in accordance with established IH guidelines and practices. In addition, the results will be communicated to Husky, site workers, and regulatory agencies as required and/or as necessary to ensure the safety and health of potentially affected individuals.

2. Exposure Standards and Guidelines

The US Occupational Health and Safety Administration provides established exposure limits for a worker's exposure to hazardous chemical substances. Additionally, Threshold Limit values (TLVs) are established by the American Conference of Governmental Industrial Hygienists (ACGIH).

These are summarized below:

Analyte	OSHA PEL		ACGIH TLV	Units
	TWA	Excursion (30 minute exposure)	TWA ¹	
Asbestos	0.1 f/cc	1.0 f/cc	0.1 f/cc	Fibers per cubic centimeter of air.

2.1 Perimeter Exposure Monitoring Criteria

During asbestos abatement activities, work area perimeter air monitoring will be performed to ensure that engineering controls prevent the release of asbestos fibers from the work area. If ambient air samples exceed the accepted asbestos clearance criterion of 0.01 f/cc (AHERA standard for building re-occupancy), work will be halted and controls (wetting, covering or wrapping damaged materials, etc.) will be put in place. Work will not restart until work practices and/or engineering controls are modified to ensure perimeter concentrations do not exceed the clearance criterion.



2.2 Personal Air Monitoring and Bulk Sampling Methods

During asbestos abatement activities, OSHA methods ID160 (personal air monitoring) and ID191 (bulk sampling) will be followed. The collection of air monitoring samples will be completed using calibrated personal sampling pumps with 25-mm diameter cassettes with mixed-cellulose ester (MCE) filters and analyzed by PCM. All sampling results will be communicated to abatement personnel in compliance with applicable regulations.

3. Quality Assurance/Quality Control (QA/QC) and Reporting

Data collected will be stored in an on-site electronic archive. The monitoring/sampling data will be entered into an electronic database (spreadsheet or equivalent), and will undergo a quality assurance and quality control (QA/QC) review. Data entry forms and field notes will be kept on-site and retained for reference upon completion of the project. If necessary, full laboratory analysis data packages will be provided, and associated data validation processes will be arranged.

During the project, interim reporting of results may be required. This may include data summaries, maps, or other presentations of preliminary monitoring and sampling results. For example, a data summary will be provided to SRC every 24 hours, once data have undergone an initial QA/QC. Such reporting will be considered preliminary, as a final QA/QC of the data will not be complete. At the completion of the project, a report will be prepared in which data collected through monitoring and integrated sampling analyses will be compiled, summarized, and reported to SRC. Data contained in the final report will have been through the QA/QC process, will be reviewed by a Certified Industrial Hygienist (CIH), and will be considered final.



4. Asbestos Abatement / Cleanup Plan

There are several considerations for addressing damage to ACM during the recovery and repair operations to be conducted at and surrounding the plant. In order of importance, asbestos activities will be conducted to:

1. Address insulation that is off site or outside the refinery boundaries as a result of the incident. In instances observed to date, the insulation outside the refinery boundary or off refinery property is not suspect ACM. However, as a conservative response, insulation from the incident that is identified outside the refinery property will be collected for proper disposal.
2. Small-scale, short duration asbestos abatement activities needed to accommodate mechanical or process activities required to stabilize and de-energize refinery equipment and piping.
3. Large-scale cleanup of asbestos-containing debris, removal of asbestos-insulated equipment that is scheduled for demolition, removal and disposal of asphalt that may be contaminated with asbestos due to damage to mechanical equipment insulation.

4.1 Offsite / Extra-refinery Cleanup

Off-site cleanup of potential ACM debris from the refinery will be accomplished using the site embedded asbestos abatement contractor or other Wisconsin-licensed asbestos abatement contractor. The contractor will perform the cleanup of ACM primarily using manual methods.

As a conservative measure, materials identified offsite will be assumed to be ACM, and packaged and disposed of as such. Representative samples of collected materials will be taken for laboratory analysis to determine asbestos content. A general map will be generated to identify locations where debris has been located offsite.

Work methods and personal protective equipment (PPE) will be selected and utilized in accordance with existing regulations and based on the asbestos abatement contractor personnel exposure monitoring program records.

Should any pieces of metal that may be considered "evidence" be encountered during offsite insulation cleanup, the location will be recorded via GPS coordinates and Baker Engineering and Risk Consultants (BakerRisk) will be contacted to facilitate removal of evidence pursuant to the General Protocol for Identification and Collection of Evidence Items.

4.2 Small-Scale, Short Term Abatement

As may be required, and similar to routine maintenance, the operations and mechanical organizations will require limited scope asbestos abatement of mechanical equipment to accommodate the process of draining, de-energizing, and stabilizing the plant equipment. To accomplish this, the mechanical and process planners will coordinate directly with the abatement contractor to scope and schedule the smaller projects. This coordination will include measures (such as exclusion zones, barrier tape, and/or signage) to minimize the risk of exposure to non-abatement personnel.



The abatement contractor will make available adequate personnel to accommodate the limited abatement.

Abatement methods and techniques will vary and may include glovebag removal, mini enclosures, wrap and cut (whole pipe removal) or other methods as appropriate and as allowed by applicable regulations; provided, however that GHD will inform and receive consent from BakerRisk before removal of piping, process equipment, or structural components. All collected insulation materials will be packaged and disposed as ACM.

Should any pieces of metal that may be considered "evidence" be encountered during offsite insulation cleanup, the location will be recorded via GPS coordinates and Baker Engineering and Risk Consultants (BakerRisk) will be contacted to facilitate removal of evidence pursuant to the General Protocol for Identification and Collection of Evidence Items.

Decontamination procedures following abatement may vary from standard abatement decontamination. Decontamination facilities typical for asbestos abatement (multiple stage structures with showers) will be available and will be utilized. It may be necessary to perform additional decontamination steps to address the presence of asphalt throughout the work areas. The need for additional decontamination steps will be determined prior to the start of any individual project and any decontamination procedure outside the routine change and shower asbestos procedure will be performed with the assistance of SRC personnel and facilities.

4.3 General Asbestos Abatement and Site Cleanup

Once the site has been stabilized and equipment has been drained and de-energized, general site abatement and cleanup will commence. To the extent practicable, ACM that can be removed will be removed prior to conducting demolition activities that may disturb ACM. If limited demolition activities are required to gain access for ACM to be removed, work will be done in such a manner to minimize the risk of exposure. The work will include measures (such as exclusion zones, barrier tape, and/or signage) to minimize the risk of exposure to non-abatement personnel.

The cleanup methods to be utilized will, to some extent, be determined by successful methods that were developed during the work performed in previous remedial work phases. Those methods may include glovebag, enclosure removal, and alternative methods approved by the Wisconsin Department of Natural Resources. Large-scale removal of asphalt will require the use of heavy equipment. All collected insulation materials will be packaged and disposed as asbestos-containing materials.

Personal decontamination procedures following abatement may vary from standard abatement decontamination, but will generally follow decontamination procedures accordance with 29 CFR 1910.120 (k). Decontamination facilities typical of asbestos abatement (multiple stage structures with showers) will be available and will be utilized. It may be necessary to perform additional decontamination steps to address the presence of asphalt throughout the work areas. The need for additional decontamination steps will be determined prior to the start of any individual project and any decontamination procedure outside the routine change and shower asbestos procedure will be performed with the assistance of Husky personnel and facilities.



Decontamination measures will be implemented to prevent contaminant tracking on and off Site. Vehicles, equipment, and workers leaving areas of potential contamination will exit through a Decontamination Reduction Zone (DRZ) prior to entry into Clean Zones from the Exclusions Zones. The DRZ will contain an equipment decontamination pad to accommodate the largest piece of on Site potentially contaminated equipment. The decontamination pad will be formed with a bed and berm, overlain by one layer of high-density polyethylene sloping toward a sump. The DRZ will provide, operate, and maintain portable, high pressure, wash units. The DRZ will maintain necessary equipment, pumps, and piping required to collect and contain equipment decontamination wastewater and sediment and transfer same to approved storage facilities. Decontamination facilities and work activities will be sequenced to prevent contaminant tracking

Copy

An MOC was held to discuss the deinventorying of the Main Column Overhead Receiver

The water boot drain line will be used to drain the Main Column Overhead Receiver. A vac truck will be connected to the drain line to remove the liquid that cannot be gravity drained from the vessel. Once the hydrocarbon is drained from the vessel the vac truck will be disconnected and a firewater hose will be connected to the drain line. Firewater will be used to flush the receiver. An operator will be monitoring the water entering the vessel by monitoring the sight glasses on the water boot and on the receiver. The vac truck will be reattached so the water can be drained from the receiver. A nitrogen sweep will be maintained on the system to ensure the draining of the receiver will not cause air to enter the system while draining.

A nitrogen purge will remain on the system after the draining procedure is completed.

A plan will be developed to send the hydrocarbon waste to either a frac tank or directly to a slop tank.

Process Engineering has been working with Operations to identify the proper valves to use for this process. P&IDs will be provided to operators for verification.

Per de-inventorying procedure, a fire plan will be put in place before the wash starts, and fire blankets will be provided as necessary for operations to work around the residual asphalt on the ground. All other standard occupational safety procedures identified will be followed as relevant, including asbestos abatement plans, vac truck bonding and grounding, pre-fire plan and environmental waste disposal.

The operators will follow the written procedure for this process, and any deviations to the procedure will be discussed by at least 3 competent personnel and will be tracked using the "proposed procedure change form" that is attached to the excessing procedure.

A contingency plan that includes a "All Stop" will be developed in the event of a material release.

Copy
SUPERIOR REFINERY/MANAGEMENT OF CHANGE (MOC)

Section 1

DESCRIPTION OF PROPOSED CHANGE

MOC No: 2493

Title of Change: Deinventorying the Main Column Overhead Receiver

Change Coordinator: Aaron Laszewski

Date: 5-18-2018

Unit: FCCU

Type of Change

Equipment Change	Procedure /Operations Change
<input type="checkbox"/> What-If Checklist (PHA) or Hazop Note: PHA required for design changes. Note: What-If Checklist is attached to the end of this document when needed.	<input checked="" type="checkbox"/> PROCEDURE / OPERATIONS
<input checked="" type="checkbox"/> PSR (Pre-Start up always Reg.)	<input type="checkbox"/> S/D CONTROLS / SIS / LIMITS / S/D Interlocks
	<input type="checkbox"/> OTHER

Duration: ☐ Permanent ☐ Permanent Shutdown ☒ Temporary (6 Months) ☐ Temporary Shutdown (Requires S/D to complete)

Description: (attach detailed information) Deinventorying the Main Column Overhead Receiver

Technical Basis for Change: (design considerations) Cannot make the receiver hydrocarbon free through normal means – Deviation from normal procedure.

Approval in the off-hours and Emergency – When changes are required in the off-shift hours or in an emergency the Refinery Shift Superintendent has the authority to authorize the change.

Section 2

MOC Team

MOC TEAM (Individuals impacted by change that may need to be involved in the PHA or Pre-Startup Review)

X if YES	DEPARTMENT	Name	X if YES	DEPARTMENT	Name
<input type="checkbox"/>	Rotating Equipment		<input type="checkbox"/>	Shift Supervisor	
<input type="checkbox"/>	Electrical		<input type="checkbox"/>	Inspection	
<input type="checkbox"/>	Maint Engr		<input checked="" type="checkbox"/>	Safety	Tim Murphy Eddie Ramirez
<input type="checkbox"/>	Project Engr		<input type="checkbox"/>	Environmental	
<input checked="" type="checkbox"/>	Process Engr	Aaron Laszewski Zak Fredericks	<input checked="" type="checkbox"/>	PSM/RMP	Becki Meyers
<input type="checkbox"/>	Maint Supervisor		<input type="checkbox"/>	Area Superintendent	
<input type="checkbox"/>	Instrumentation		<input checked="" type="checkbox"/>	Operations Manager	Brian McCusker
<input type="checkbox"/>	Advanced Controls		<input type="checkbox"/>	Contractor	
<input checked="" type="checkbox"/>	Operation Rep	Keith Nordskog	<input type="checkbox"/>		

SUPERIOR REFINERY MANAGEMENT OF CHANGE (MOC)

ISSUES FOR DISCUSSION EXPANDED TO MORE SPECIFIC QUESTIONS

A. Process Safety Information

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>	Alarm Rationalization & Priorities Established and Set In DCS		
<input type="checkbox"/>	<input type="checkbox"/>	Cause & Effect Diagrams		
<input type="checkbox"/>	<input type="checkbox"/>	DCS Graphics Update		
<input type="checkbox"/>	<input type="checkbox"/>	Elec. Area Class Drawing		
<input type="checkbox"/>	<input type="checkbox"/>	Electrical One Lines		
<input type="checkbox"/>	<input type="checkbox"/>	Equipment Limits & Design Codes		
<input type="checkbox"/>	<input type="checkbox"/>	Superior EP's Followed-Deviations		
<input type="checkbox"/>	<input type="checkbox"/>	Line Sloped (i.e. flare headers)		
<input type="checkbox"/>	<input type="checkbox"/>	Material & Energy Balance		
<input type="checkbox"/>	<input type="checkbox"/>	P&IDs		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	P&ID's Available to Operations (Red lines OK)	Aaron Laszewski	
<input type="checkbox"/>	<input type="checkbox"/>	PFD		
<input type="checkbox"/>	<input type="checkbox"/>	Plot Plan		
<input type="checkbox"/>	<input type="checkbox"/>	Maximum Inventory Update		
<input type="checkbox"/>	<input type="checkbox"/>	PI Data		
<input type="checkbox"/>	<input type="checkbox"/>	Process Chemistry		
<input type="checkbox"/>	<input type="checkbox"/>	PSV Database Design Basis		
<input type="checkbox"/>	<input type="checkbox"/>	Safe Operating Limits		
<input type="checkbox"/>	<input type="checkbox"/>	Verify Flare Capacity Study is Current		
<input type="checkbox"/>	<input type="checkbox"/>	Equipment/line#/Index Database Update		
<input type="checkbox"/>	<input type="checkbox"/>			

B. Process Hazards Analysis

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Action	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>	Car Seal List		
<input type="checkbox"/>	<input type="checkbox"/>	Design Changes Were Re-Hazoped		
<input type="checkbox"/>	<input type="checkbox"/>	LOPAs Completed		
<input type="checkbox"/>	<input type="checkbox"/>	PHA Completed as Required		
<input type="checkbox"/>	<input type="checkbox"/>	PHA Recommendations Complete		
<input type="checkbox"/>	<input type="checkbox"/>	RMP Update		
<input type="checkbox"/>	<input type="checkbox"/>			

C. Health Issues

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Asbestos/Lead Paint Program	GHD	
<input type="checkbox"/>	<input type="checkbox"/>	Employee Exposure & Personal Monitoring/Records		
<input type="checkbox"/>	<input type="checkbox"/>	HAZCOM Equipment Labels		

SUPERIOR REFINERY MANAGEMENT OF CHANGE (MOC)

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Proper PPE Identified	Tim Murphy	
<input type="checkbox"/>	<input type="checkbox"/>	SDS list		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Stenciling/Labeling – Nitrogen line to MC/Flare	Keith Nordskog	
<input type="checkbox"/>	<input type="checkbox"/>	Building/Trailer Siting		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Fire Blanketing provided as necessary	GHD	

D. Environmental Issues

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>	CEMS installed and calibrated correctly		
<input type="checkbox"/>	<input type="checkbox"/>	LDAR Field Tags & Data Base Updated		
<input type="checkbox"/>	<input type="checkbox"/>	Marked Up P&ID received by LDAR Before S/U		
<input type="checkbox"/>	<input type="checkbox"/>	Notify LDAR group when system is starting		
<input type="checkbox"/>	<input type="checkbox"/>	Provide Marked up P&ID to LDAR Before S/U		
<input type="checkbox"/>	<input type="checkbox"/>	RATA/Ops. Env.		
<input type="checkbox"/>	<input type="checkbox"/>	Sewer PTI - Verify if Leak Test is Required		
<input type="checkbox"/>	<input type="checkbox"/>	Shutdown/Startup Checklist (SSM)		
<input type="checkbox"/>	<input type="checkbox"/>	Title V Update/PTI and/or Update		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Waste Disposal – Frac tank or slop tank	Aaron Laszewski	
<input type="checkbox"/>	<input type="checkbox"/>	BWON Waste Stream Additions		
<input type="checkbox"/>	<input type="checkbox"/>	QQQ Drain Impacts		
<input type="checkbox"/>	<input type="checkbox"/>	Environmental Permit Triggers		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Air Monitoring	GHD	

E. Mechanical Integrity

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
PIPING & STATIONARY EQUIPMENT –				
<input type="checkbox"/>	<input type="checkbox"/>	Inspection Drawings		
<input type="checkbox"/>	<input type="checkbox"/>	Flange Management - Bolts Torqued per Requirements		
<input type="checkbox"/>	<input type="checkbox"/>	Chain Wheel Operators		
<input type="checkbox"/>	<input type="checkbox"/>	Clamp List		
<input type="checkbox"/>	<input type="checkbox"/>	CUI Removed or Protected		
<input type="checkbox"/>	<input type="checkbox"/>	Dead Legs		
<input type="checkbox"/>	<input type="checkbox"/>	Field Inspection (QA/QC) Reports		
<input type="checkbox"/>	<input type="checkbox"/>	Gaskets & Packings Checked		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Grounding Wires – Vac Truck	Eric Barnard	
<input type="checkbox"/>	<input type="checkbox"/>	Inspection PSV/TRV Database		
<input type="checkbox"/>	<input type="checkbox"/>	Inspection Recommendations		
<input type="checkbox"/>	<input type="checkbox"/>	Insulation Installed		
<input type="checkbox"/>	<input type="checkbox"/>	Maint. Tightness Check		
<input type="checkbox"/>	<input type="checkbox"/>	Operations Tightness Check		
<input type="checkbox"/>	<input type="checkbox"/>	PMI (Positive Material Identification) Completed		
<input type="checkbox"/>	<input type="checkbox"/>	Protective Coatings		
<input type="checkbox"/>	<input type="checkbox"/>	Valve Bench PSV Test Reports		
<input type="checkbox"/>	<input type="checkbox"/>	Vendor Drawings		
<input type="checkbox"/>	<input type="checkbox"/>	Vessel/Pipe Shop Insp. package		

SUPERIOR REFINERY MANAGEMENT OF CHANGE (MOC)

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>			
<input type="checkbox"/>	<input type="checkbox"/>			
CONTROLS				
<input type="checkbox"/>	<input type="checkbox"/>	Alarm Database Update		
<input type="checkbox"/>	<input type="checkbox"/>	Alarm Response Update		
<input type="checkbox"/>	<input type="checkbox"/>	Calibration & Testing Data		
<input type="checkbox"/>	<input type="checkbox"/>	Control System FAT/SAT Reports		
<input type="checkbox"/>	<input type="checkbox"/>	Critical/Testing Reports Complete		
<input type="checkbox"/>	<input type="checkbox"/>	EIV Field Tests		
<input type="checkbox"/>	<input type="checkbox"/>	EIV PM Database Update		
<input type="checkbox"/>	<input type="checkbox"/>	Loop Folders & Test Reports		
<input type="checkbox"/>	<input type="checkbox"/>	SIS Database and Field Testing		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Pressure gauges to monitor MC and Flare purge	Keith Nordskog	
ELECTRICAL				
<input type="checkbox"/>	<input type="checkbox"/>	Cathodic Protection		
<input type="checkbox"/>	<input type="checkbox"/>	Electric Heat Trace Test Reports		
<input type="checkbox"/>	<input type="checkbox"/>	Equipment Files		
<input type="checkbox"/>	<input type="checkbox"/>	Field Test Reports		
<input type="checkbox"/>	<input type="checkbox"/>	Protective Relay Settings		
<input type="checkbox"/>	<input type="checkbox"/>	Max AMP Level Established		
<input type="checkbox"/>	<input type="checkbox"/>	Mfgr. Test Reports Received		
<input type="checkbox"/>	<input type="checkbox"/>	Field Equipment Labeling		
<input type="checkbox"/>	<input type="checkbox"/>	Motor Database Update		
<input type="checkbox"/>	<input type="checkbox"/>			
ROTATING EQUIPMENT				
<input type="checkbox"/>	<input type="checkbox"/>	Equipment Files		
<input type="checkbox"/>	<input type="checkbox"/>	Field Final Alignment & settings		
<input type="checkbox"/>	<input type="checkbox"/>	Lubricants & Fluids at Level		
<input type="checkbox"/>	<input type="checkbox"/>	Vibration Probes Functional		
<input type="checkbox"/>	<input type="checkbox"/>			
MECHANICAL INTEGRITY GENERAL				
<input type="checkbox"/>	<input type="checkbox"/>	Change in PM Schedule Identified		
<input type="checkbox"/>	<input type="checkbox"/>	Enter a SAP WO for Shutdown Worklist		
<input type="checkbox"/>	<input type="checkbox"/>	Spare Parts On-Hand		
<input type="checkbox"/>	<input type="checkbox"/>	Vessel Media Inspected		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Add temporary lines, check valve in nitrogen line – work order	Aaron Laszewski	
<input type="checkbox"/>	<input type="checkbox"/>			

F. Operating & Maintenance Procedures

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
OPERATING PROCEDURES				
<input type="checkbox"/>	<input type="checkbox"/>	Emergency Operations		
<input type="checkbox"/>	<input type="checkbox"/>	Emergency Shutdown		
<input type="checkbox"/>	<input type="checkbox"/>	Initial Startup		
<input type="checkbox"/>	<input type="checkbox"/>	Normal Operations		

SUPERIOR REFINERY MANAGEMENT OF CHANGE (MOC)

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>	Normal Shutdown		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Temporary Operations	Aaron Laszewski	
<input type="checkbox"/>	<input type="checkbox"/>	Turnaround Startup		
<input type="checkbox"/>	<input type="checkbox"/>	Will change effect S/D, S/U or bypass operations		
OPERATING LIMITS				
<input type="checkbox"/>	<input type="checkbox"/>	Operations Alarm Response		
<input type="checkbox"/>	<input type="checkbox"/>			
MAINTENANCE PROCEDURES/PROGRAMS				
<input type="checkbox"/>	<input type="checkbox"/>	Procedures Updated or Developed		
<input type="checkbox"/>	<input type="checkbox"/>			
GENERAL				
<input type="checkbox"/>	<input type="checkbox"/>	Blind List Updates/Change		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Isolation/LOTO Plan	Keith Nordskog	
<input type="checkbox"/>	<input type="checkbox"/>	Unit Checklist/Log Sheets (Outside & Control) Updated		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Procedure deviation tracking	Aaron Laszewski	

G. Training

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>	Contractor Training		
<input type="checkbox"/>	<input type="checkbox"/>	Training Database Updated		
<input type="checkbox"/>	<input type="checkbox"/>	Maintenance Training		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Notification	Pete Raboin	
<input type="checkbox"/>	<input type="checkbox"/>	Operations Training		
<input type="checkbox"/>	<input type="checkbox"/>	Training Manual/Drawings Updated		
<input type="checkbox"/>	<input type="checkbox"/>			

H. Pre-Startup Safety Review

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>	Equipment Service Contracts		
<input type="checkbox"/>	<input type="checkbox"/>	Extra Startup Manpower		
<input type="checkbox"/>	<input type="checkbox"/>	Inspection and Testing Complete		
<input type="checkbox"/>	<input type="checkbox"/>	Pre-Startup Walk-Through & Punchlist		
<input type="checkbox"/>	<input type="checkbox"/>	Field Post-Startup Punch List (for applicable projects)		
<input type="checkbox"/>	<input type="checkbox"/>			

SUPERIOR REFINERY MANAGEMENT OF CHANGE (MOC)

I. Work Authorization

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>	Blind Lists for Work		
<input type="checkbox"/>	<input type="checkbox"/>	Confined Space Entry		
<input type="checkbox"/>	<input type="checkbox"/>	Hot Tapping		
<input type="checkbox"/>	<input type="checkbox"/>	Hot Work		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Job Hazard Analysis (JSA/JSR)	Aaron Laszewski	
<input type="checkbox"/>	<input type="checkbox"/>	LOTO		
<input type="checkbox"/>	<input type="checkbox"/>			

J. Contractors

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Contractor Communication/Notifications	Aaron Laszewski	
<input type="checkbox"/>	<input type="checkbox"/>			

K. Safety & Emergency Planning and Response

Also review all outstanding items from previous PSRs and PHA.

Pre S/U	Post S/U	Update Existing / Create New	Assigned To / Completed By	Date Completed
<input type="checkbox"/>	<input type="checkbox"/>	Emergency Response Drills/Training		
<input type="checkbox"/>	<input type="checkbox"/>	Emergency Response Plan (ERP)		
<input type="checkbox"/>	<input type="checkbox"/>	Fire Response Equipment & Inspection Records		
<input checked="" type="checkbox"/>	<input type="checkbox"/>	Pre-Fire Plans	Jerome Quimby	
<input type="checkbox"/>	<input type="checkbox"/>	Safety Equipment (SCBA, Showers, PPE)		
<input type="checkbox"/>	<input type="checkbox"/>	Update changes to SPIs or Procedures		
<input type="checkbox"/>	<input type="checkbox"/>			

SUPERIOR REFINERY MANAGEMENT OF CHANGE (MOC)

Section 3

APPROVAL TO INSTALL

Area Supervisor or Other Approving Authority

Date

Section 4

APPROVAL TO STARTUP (Follows PSR 5 Pre-Startup Safety Review) Prior to filling out this, all Pre-Startup Action Items should be completed. Review PSR 5 and other previous PSRs.

Operations Manager or Other Approving Authority

Date

Section 5

FINAL DOCUMENTATION COMPLETE

This section should not be filled in until all agreed-upon post startup activities should be completed.
Review Pre-startup documents and MOC open items from previous PSRs and PHA.

Change / Project Coordinator

Date

(Maintenance, Project or Process engineers, etc.)



Flammability & Explosion Hazard Assessment

CHARM Modeling Simulations – FCC/Gas Con Main Column Overhead Receiver

To: Zac Fredericks (Barr/Husky)

Cc: Chip Day, SRS

From: Scott Skelton, MS, CIH

Date: May 17, 2018

Re: Summary report for dispersion modeling simulations analyzing flammability risk

1 Introduction

Chemical inventory assessment conducted post-fire suggest that flammable gas and flammable liquids remain in piping, vessels, and other process equipment in varying quantities. During the de-inventory process, flammable liquids and gas will be removed from affected refinery installations using closed-loop machinery and equipment with vapor controlled by a portable flare capable of generating ignition in a flammable atmosphere. In support of safe-work practices during de-inventory, Specialized Response Solutions (SRS) has conducted air dispersion modeling to simulate release of flammable liquids and gases to assess the potential for flammable atmospheres near potential ignition sources. Air dispersion simulations were run using the Complex Hazardous Air Release Model (CHARM™), which is a computer-based software that uses Eulerian Grid puff-to-plume algorithms to depict downwind chemical mass transport.

2 Chemical Selection

Natural gasoline has been identified as the primary liquid stream currently in the process units along with a small vessel containing propane at a pressure of 100 psi. The chemicals selected for simulations include: naphtha and gasoline as surrogates reflecting the chemical property range of natural gasoline, and propane as the flammable gas contained in the Merox vessel stored at 100 psi.

3 Simulation Scenarios

The following scenarios describe the basis for the release characteristics, which are intended to represent a worst-case scenario during de-inventory activities.

1. Propane

- a. Site personnel identified a stored volume of propane gas in the Merox vessel measuring 48" in diameter and approximately 13' 11.5" in height. The total pressure on the vessel was observed at 100 psi.
- b. The release scenario depicts a catastrophic failure of containment resulting in depressurization of the vessel to atmospheric pressure (14.7 psi), indicating that all contained propane is released into the work area.

2. Naphtha

- a. The process equipment contained a gasoline range liquid prior to the facility fire. Although it can be loosely identified as a natural gasoline, there remains no information on the exact speciation of the hydrocarbon mixture. The lower end of natural gasoline's flammable range is best represented in chemical properties by petroleum distillates otherwise known as naphtha.
- b. The naphtha simulation involves an instantaneous release of 1000 US gallons onto the ground resulting in a pool of flammable liquid approximately 63 feet in diameter and 0.5 inches deep.

3. Gasoline

- a. The process equipment contained a gasoline range liquid prior to the facility fire. Although it can be loosely identified as a natural gasoline, there remains no information on the exact speciation of the hydrocarbon mixture. The upper bound of natural gasoline's flammable range is best represented in chemical properties by gasoline, which also exhibits a slightly higher lower flammable range and flash point when compared to naphtha.
- b. The gasoline simulation involves an instantaneous release of 1000 US gallons onto the ground resulting in a pool of flammable liquid approximately 63 feet in diameter and 0.5 inches deep.

4. Gasoline Pool Fire


- a. The stabilization and manipulation of compromised process lines; sumps or vessels may lead to the unintended release of flammable hydrocarbon liquid and vapor. The potential for ignition exists during mechanical manipulation of process equipment. The gasoline pool fire simulation is intended to represent the thermal energy emitted during combustion of the flammable vapor directly above the pooled gasoline.
- b. Simulations were run for 1,000 gallons of gasoline to depict a reasonable range of worst-case release based upon estimates of liquids in the FCC Gas Con unit.

4 Results

4.1 Propane

The highest concentration predicted for airborne propane extends 8 feet from the Merox vessel at a height of 8 feet above grade. The maximum concentration predicted resulted in approximately 52,000 ppm (5.2%), which exceeds the lower flammability limit of 21,000 ppm (2.1%). However, at the flare location the maximum concentration predicted for propane resulted in approximately 182 ppm (well below the lower flammability limit of propane) at a time period of 90 seconds post-release. This significant reduction in airborne concentration from the source is due to the effect of air entrainment-induced dilution of the migrating plume.

Merco Vessel Propane - Flare Protection
Species: Propane
Met:Sunny_warm_very unstable
Grid:Default Grid



Integrated Plume
Time: 02:00
Height: 8 ft
Above Ground
Radius: 488 ft
Increment: 100 ft
Plot Scale 1:2495

Hatch Conc(ppm)	Max Dist
1e+003	143 ft
2.1e+003	96 ft
2.1e+004	55 ft

Hatch Conc($\mu\text{g}/\text{m}^3$)

1.79e+006
3.76e+006
3.76e+007


Max Conc
x = 4.512e+004 ppm
Dist: 15 ft Ang: 22
Max Conc at hgt 8 ft
5.265e+004 ppm
Dist: 28 ft Ang: 34

4.2 Gasoline

The release scenario of 1000 gallons of gasoline assumes a liquid pool formation of approximately 63 feet in diameter and 0.5 inches in depth. The model also assumes the pool evaporation duration of 59 minutes at an average evaporation rate of 5,500 lbs./hour.

The highest concentration predicted for airborne gasoline vapor extends 35 feet from the FCC Gas Con Unit at a height of 3 feet above grade. The maximum concentration predicted resulted in approximately 4,088 ppm (0.4%), which is above the site action level of 1,400 ppm (10% of LEL), but below the lower flammability limit of 14,000 ppm (1.4%). However, at the flare location the maximum concentration resulted in approximately 115 ppm (well below the lower flammability limit of propane) at a time period of 3 minutes post-release. This significant reduction in airborne concentration from the source is due to the effect of air entrainment-induced dilution of the migrating plume.

Hydrocarbon Releases - Flare Protection
Species: Gasoline
Met:Sunny_warm_very unstable
Grid:Default Grid



Integrated Plume
Time: 00:10
Height: 0 ft
Above Ground
Radius: 500 ft
Increment: 100 ft
Plot Scale 1:2555

Hatch Conc(ppm)	Max Dist
200	236 ft
$1.4e+003$	72 ft
$1.4e+004$	0 ft

Hatch Conc($\mu\text{g}/\text{m}^3$)

$7.01e+005$
$4.9e+006$
$4.9e+007$

Max Conc
x = 4088 ppm
Dist: 35 ft Ang: 47
Max Conc at hgt
4088 ppm
Dist: 35 ft Ang: 47


Imagery ©2018, DigitalGlobe, USDA Farm Service Agency

4.3 Naphtha

The release scenario of 1000 gallons of naphtha assumes a liquid pool formation of approximately 63 feet in diameter and 0.5 inches in depth. The model also assumes the pool evaporation duration of 66 minutes at an average evaporation rate of 5,820 lbs./hour.

The highest concentration predicted for airborne naphtha vapor extends 47 feet from the FCC Gas Con Unit at a height of 3 feet above grade. The maximum concentration predicted is approximately 1,033 ppm, which is above the site action level of 800 ppm (10%LEL), but falls below the lower flammability limit of 8,000 ppm (0.8%). However, at the flare location the maximum concentration predicted for hydrocarbon vapor resulted in approximately 90 ppm (below the lower flammability limit of naphtha) at a time period of 2 minutes seconds post-release. This significant reduction in airborne concentration from the source is due to the effect of air entrainment-induced dilution of the migrating plume.

Hydrocarbon Release - Flare Protection
 Species: Naphtha
 Met: Sunny, warm, very unstable
 Grid: Default Grid



Integrated Plume
 Time: 00:10
 Height: 0 ft
 Above Ground
 Radius: 500 ft
 Increment: 100 ft
 Plot Scale 1:2555

Hatch Conc(ppm)	Max Dist
100	393 ft
800	63 ft
8e+003	0 ft

Hatch Conc(kg/m³)
4.1e+005
3.28e+006
3.28e+007

Max Conc
 x = 1034 ppm
 Dist: 49 ft Ang: 47
 Max Conc at hgt 3 ft
 1034 ppm
 Dist: 49 ft Ang: 47

Google

Imagery ©2018, DigitalGlobe, USDA Farm Service Agency Terms of


4.4 Gasoline Pool Fire

4.4.1 Gasoline Pool Fire – 1,000 gallon release

The model predicts a pool fire with a diameter of 43 feet of the 63 feet spill area at a consumption rate of 133,000 lbs/hr. The maximum temperature predicted is 3611 °F with an output of 588 million BTU/hr thermal output rate (172,000 kW) at a flame tilt of 40° based on the 0.5 mph wind used in the simulation. The model estimates the flame center to be 70 feet with a flame length of 139 feet and a burn time of 1.35 minutes. The model predicts a fatality rate of 1.0 (100%) to extend 48 feet from the flame center, a fatality rate of 0.99 (99%) extending 65 feet from the flame center, a fatality rate of 0.49 (49%) extending 98 feet from flame center, and a fatality rate of 0.17 (17%) extending 113 feet from the flame center. The probability of fatality is based on heat energy likely to cause fatality to an unprotected human body. The following are damaged estimates based on radiation intensity in kW/m². Source: *Guidelines for Chemical Process Quantitative Risk Analysis*, American Institute of Chemical Engineers Center for Chemical Process Safety, NY, NY, 1989. The resultant simulation distances are included as sub-set line items based on the damage estimate values.

- 1.6 - Will cause no discomfort for long exposure
 - Predicted radius: 299 feet, max height: 330 feet
- 4.0 - Sufficient to cause pain to personnel if unable to reach cover within 20 seconds; however, blistering of the skin (second degree burns) is likely; 0% lethality.
 - Predicted radius: 184 feet, max height: 224 feet
- 9.5 - Pain threshold reached after 8 seconds; second degree burns after 20 seconds.
 - Predicted radius: 113 feet, max height: 167 feet
- 12.5 - Minimum energy required for piloted ignition of wood; melting plastic tubing.
 - Predicted radius: 98 feet, max height: 167 feet
- 25.0 - Minimum energy required to ignite wood at indefinitely long exposures (non-piloted).
 - Predicted radius: 65 feet, max height: 166 feet
- 37.5 - Sufficient to cause damage to process equipment.
 - Predicted radius: 48 feet, max height: 164 feet

Main Column Overhead Receiver_1000gal
 Species: Gasoline
 Met: Gasoline_cool weather -extremely unstable-0.5mph wind
 Grid: Default Grid



Pool Fire Radiation
 Time: 00:01
 Height: 0 ft
 Above Ground
 Radius: 500 ft
 Increment: 100 ft
 Plot Scale 1:2555

Duration: 1.35 min
 Flame center: 70 ft
 Flame length: 139 ft
 Tilt: 0°
 RMP Dist: 153 ft

Flux Units: kW/m²


Hatch	Flux	Radius
	1.6	299 ft
	4	184 ft
	9.5	113 ft
	12.5	98 ft
	25	65 ft
	37.5	48 ft

Hatch	Flux	P(fatal)
	1.6	0.00
	4	0.00
	9.5	0.17
	12.5	0.49
	25	0.99
	37.5	1.00

Dose: (kW/m²)^(4/3)-sec

Hatch	Flux	Dose
	1.6	152.06
	4	515.96
	9.5	1634.93
	12.5	2357.30
	25	5940.03
	37.5	10199.45

Main Column Overhead Receiver_1000gal
Species: Gasoline
Met: Gasoline_cool weather -extremely unstable-0.5mphwind
Grid: Default Grid



Vertical X-Section
Pool Fire Radiation
Time: 00:01
Base Hgt: 0 ft
View angle: 126

Hatch	BTU/hr ft ²	Max Hgt
	508	330 ft
	1.27e+003	224 ft
	3.01e+003	167 ft
	3.97e+003	167 ft
	7.93e+003	166 ft
	1.19e+004	164 ft

Hatch	kW/m ²	Min Hgt
	1.6	0 ft
	4	0 ft
	9.5	0 ft
	12.5	0 ft
	25	0 ft
	37.5	0 ft

05 18 2018



05 18 2018



	SUPERIOR REFINERY	OPERATING PROCEDURE
	Title: De-Inventory of Main Column Receiver	
	Sub-title:	

Date written: 5/17/18

Written by: Aaron Laszewski

Approval date:

Approved by:

Revision no:

Procedure no: OPP0000

File no: o:\procedure example

Last revised date:

Revised by:

PURPOSE/SCOPE OF PROCEDURE

Draining the Main Column Overhead Receiver to a vacuum truck.

SAFETY AND HEALTH CONSIDERATIONS

Reference the Safety Data Sheet (SDS) for all chemicals/catalyst/products in the process to obtain the properties of and hazards presented by these chemicals.

Reference the control measures to be taken if physical contact or airborne exposure occurs.

Reference precautions necessary to prevent exposure including Personal Protective Equipment.

PPE requirements are defined prior to the step when requirements exceed the standard plant PPE (hard hat, safety glasses, personal H2S monitor, fire resistant clothing, and safety toe footwear with defined heel).

HAZARDS OF THE PROCESS

Grounding of Vacuum Truck (will be verified by electrician)

APPLICABLE DOCUMENTS

Safe Upper and Lower Limits tables are troubleshooting guidelines that define Process Limits, Consequences of Deviation, and the steps to avoid or correct the deviation. They are used in conjunction with Operating Procedures to respond to process deviations that have initiated a DCS alarm. Tables are found in the Superior Refinery Information Server (SIS Webpage)

REQUIREMENTS

Process Parameter Limits are defined in the DCS. Both (Advisory) high and low alarms are considered to be operational and do not indicate an emergency condition. (Critical) High/High and Low/Low alarms indicate an emergency condition and require an immediate corrective action.

If required in procedure, upon completion of each step, the operator carrying out the step shall log time & initial indicating completion of the step.

CAUTION: Any changes to content, sequence or step elimination of this procedure requires a Job Safety Review to be completed prior to implementing the change. The review of the task must include all personnel affected and at least 2 other knowledgeable subject matter experts, including Supervision.

CAUTION: An MOC is required if the procedure changes increase the risk of injury to personnel, off site environmental impact or release of Highly Hazardous Chemicals.

In general, an MOC is required if the change to the procedure defeats a shutdown, defeats a PSV, defeats any device meant to protect the unit and associated equipment, or causes exceedance of a mechanical limit, causes exceedance of a safe operating limit or introduces new chemicals to the process.

NOTE: The Shift Supervisor has the authority to approve an MOC in the off-hours and / or in the absence of the Operations manager as necessary.

☐ N/A

JOB SAFETY REVIEW OF PROPOSED PROCEDURAL CHANGES:

Print Name

Job Classification

1.0	Personnel Participating in the JSR	1.1			
		1.2			
		1.3			
2.0	Description Of Procedure Change To Be Performed Or Eliminated	<div style="border-bottom: 1px solid black; height: 15px; margin-bottom: 2px;"></div> <div style="border-bottom: 1px solid black; height: 15px; margin-bottom: 2px;"></div> <div style="border-bottom: 1px solid black; height: 15px;"></div>			
3.0	Identify Potential Hazards Associated With Changes to This Procedure	3.1 Exposure To Personnel <input type="checkbox"/> Chemical Contact <input type="checkbox"/> Particles in Eye <input type="checkbox"/> Heat / Cold <input type="checkbox"/> Radiation	<input type="checkbox"/> Thermal Burn <input type="checkbox"/> Noise <input type="checkbox"/> Lead / Asbestos <input type="checkbox"/> Inhalation	3.2 Process Hazards <input type="checkbox"/> More Flow <input type="checkbox"/> More Pressure <input type="checkbox"/> More Level <input type="checkbox"/> More Temperature <input type="checkbox"/> Hydraulic Hammer <input type="checkbox"/> Overfilling <input type="checkbox"/> Overheating <input type="checkbox"/> Pulling Vacuum <input type="checkbox"/> Gas ingress <input type="checkbox"/> Loss of containment	<input type="checkbox"/> Less Flow <input type="checkbox"/> Less Pressure <input type="checkbox"/> Less Level <input type="checkbox"/> Less Temperature <input type="checkbox"/> Flow Surge <input type="checkbox"/> Loss of level <input type="checkbox"/> Over cooling <input type="checkbox"/> Air ingress <input type="checkbox"/> Environmental
		3.3 Fire Hazards <input type="checkbox"/> Mixing Chemicals <input type="checkbox"/> Spills	<input type="checkbox"/> Fire / Explosion <input type="checkbox"/> Runaway reaction		
		3.4 Other Hazards <input type="checkbox"/> Human Factors <input type="checkbox"/> Process Interruption in adjacent area	<input type="checkbox"/> Dropped Objects		
4.0	List And Describe Potential Hazards	<div style="border-bottom: 1px solid black; height: 15px; margin-bottom: 2px;"></div> <div style="border-bottom: 1px solid black; height: 15px; margin-bottom: 2px;"></div> <div style="border-bottom: 1px solid black; height: 15px;"></div>			
5.0	Recommendations To Remove Hazards	<div style="border-bottom: 1px solid black; height: 15px; margin-bottom: 2px;"></div> <div style="border-bottom: 1px solid black; height: 15px; margin-bottom: 2px;"></div> <div style="border-bottom: 1px solid black; height: 15px;"></div>			

NOTE: Use the back side of this sheet if additional space is required.

	SUPERIOR REFINERY	OPERATING PROCEDURE
	Title: De-Inventory of Main Column Receiver	
	Sub-title:	

PROCEDURE:

CAUTION: ANY VALVE POSITION CHANGES MUST BE DOCUMENTED AND TAGGED FOR THE INTEGRITY OF THE INVESTIGATION.

CAUTION: DO NOT MOVE ANY CHEMICAL CLEANING EQUIPMENT/CONNECTIONS WITHOUT PRIOR AUTHORIZATION FROM BILL DEMCHUCK (HUSKY LEAD INVESTIGATOR) OR BILL'S RELIEF.

TIME INITIAL

_____ 1. Connect nitrogen hose to ¾" bleeder on suction side of B-Compressor

_____ 2. Start flowing nitrogen at 2-5 psig at inlet into process.

NOTE: WE ARE TRYING TO ADD ENOUGH NITROGEN TO PREVENT ADDITIONAL AIR INTAKE WHILE DRAINING THE LIQUID OUT OF THE MAIN COLUMN RECEIVER. WE DO NOT WANT TO BUILD SIGNIFICANT BACK PRESSURE AS THAT MY FORCE HYDROCARBONS OUT.

_____ 3. Close all suction valves of the wet gas compressors

1.31 Suction Valve A Compressor

1.32 Suction Valve B Compressor

1.33 Suction Valve C Compressor

_____ 4. Close Block valves on receiver pressure control spill back control valve

NOTE: WE WANT TO PURGE NITROGEN INTO THE TOP OF THE MAIN COLUMN RECEIVER AND NOT THE GAS CON. THAT IS WHY WE ARE ISOLATING THE GAS CON FROM THE MAIN COLUMN

_____ 5. Block in downstream valve and bypass valve on the main column overhead receiver level control valve

_____ 6. Connect vacuum truck hose to Main Column Drain 1 and drain.

_____ 7. Connect fire water to Water Inlet 1

_____ 8. Fill Main Column Overhead Receiver with firewater until a water level can be seen in the Main Column sight glass

NOTE: WE ARE TRYING TO FLOW ALL OF THE HYDROCARBON FROM THE DEAD LEGS IN THE FIRE AFFECTED ZONE BACK TO THE MAIN COLUMN RECIEVER

_____ 9. Let the water sit for 1 hour.


	SUPERIOR REFINERY	OPERATING PROCEDURE
	Title: De-Inventory of Main Column Receiver	
	Sub-title:	

NOTE: THIS ONE HOUR WATER PERIOD WOULD BE A GOOD TIME TO HAVE THE VACUUM TRUCK OFFLOAD THE BULK HYDROCARBON TO THE SLOP. THE NEXT VACUUM TRUCK LOAD WILL BE PRIMARILY WATER.

_____ 10.Drain Main Column Drain 1.


_____ 11.Continue nitrogen purge from the wet gas compressors to the main column.


END OF PROCEDURE



**Main Column Overhead
Receiver De-Inventory Plan
Aaron Laszewski**

REV.	DATE	INITIALS	DESCRIPTION	EQUIPMENT	SUPERIOR REFINERY SUPERIOR, WISCONSIN	
Q	08/02/11	PMZ	TRUE UP	15F-P10A NET OVERHEAD PUMP		
R	03/13/12	BM/PMZ	MOC 1840	15F-P10B NET OVERHEAD/MAIN COLUMN REFLUX SPARE PUMP	FLUID CATALYTIC CRACKING UNIT FRACTIONATION SECTION PIPING AND INSTRUMENT DIAGRAM	
S	09/22/15	MAM	MOC 2155	15F-P9 MAIN COLUMN REFLUX PUMP		
T	09/14/16	AC	MOC 2249		DRAWN BY RON NELSON 01/07/93	SCALE N° NE
					CHECKED BY RON NELSON 03/14/95	DATE
					APPROVED BY BRIAN M. 03/21/95	DRAWING NO.
					INITIALS	SD 15F 200 SHT 16





**Main Column Receiver
De-inventory**

LEGEND

- MACT VOC-L
- MACT VOC-G
- V^c-L
- VOC-G
- STEAM/WATER
- NATURAL GAS
- NOT IN LDAR PROGRAM

NOTE 1
1\"/>

15F-P28
WASTE WATER PUMP
DESIGN CAPY: 40 GPM @ 120 TDH
DRIVER: 5 HP 3505 RPM
SEAL TYPE: JOHN CRANE 9 1 1/2\"/>

15F-P11
WASTE WATER PUMP
DESIGN CAPY: 40 GPM @ 120 TDH
DRIVER: 5HP ELECTRIC: 3800 RPM
SEAL TYPE: JOHN CRANE 9 1 1/2\"/>


REV.	DATE	INITIALS	DESCRIPTION	EQUIPMENT
I	12/14/04	PMZ	LDAR	15F-V15
J	04/18/05	PMZ	MOC 1392 / LDAR	MAIN C ^o LUMN OVERHEAD RECEIVER
K	04/25/06	PMZ	LDAR	15F-11
L	12/19/06	PMZ	LDAR	WASTE WATER PUMP
M	06/23/08	PMZ	MOC 1495	
N	02/05/09	PMZ	LDAR	
O	08/11/11	PMZ	LDAR TRUE UP	
P	01/23/12	PMZ	TRUE UP	
Q	03/13/12	BM/PMZ	MOC 1840	
R	06/21/13	BJM	MOC 1894	
S	06/20/14	PJM	MOC 2132	
T	03/12/15	EB/PJM	MOC 2319	
U	11/29/16	BM/PJM		

SUPERIOR REFINERY SUPERIOR, WISCONSIN		FLUID CATALYTIC CRACKING UNIT FRACT ^o NAT ^o N SECT ^o N PIPING AND INSTRUMENTATI ^o N DIAGRAM	
		DRAWN BY ED SMITH 08/08/94 CHECKED BY KEN RIKK ^o LA APPROVED BY BRIAN M. INITIALS	SCALE NONE DATE DRAWING NO. SD 15F 200 SHT 20

De-Inventory Fire Plan

FIRE TRUCK WILL
BE POSITIONED BY
#1 COOLING TOWER
(STAND BY)
NOTE: WIND DIRECTION
MAY ALTER
PLAN (SLIGHTLY)

Equipment to
de-inventory
Pathway to
equipment
Asphalt removal




Main Column Overhead Receiver De-Inventory (equipment staging/air monitoring)

- additional areaRAE
as needed due to wind
or west of tank.

Vac Truck and
Connections

Nitrogen Trailer
Connections



5-19-2018

	INSPECTION	OVERVIEW	INSPECTION				OVERVIEW	INSPECTION			OVERVIEW	INSPECTION	OVERVIEW	OPERATIONS		OVERVIEW	OPERATIONS		OVERVIEW
	Foundation Assessment	Remarks	Ladders / Platforms Assessment	Small Bore Piping Assessment	Electrical Instrumentation Assessment	Insulation Intact? Asbestos?	Remarks	Visible Shell Damage (Yes / No)	Visible Structural Damage (Yes / No)	Visible Product Leaking? (Yes / No)	Remarks	ITP / RR Complete	Remarks	Contains Product? (Yes / No)	Product Level (Enter Level)	Remarks	Still Pressurized? (Yes / No)	Pressure (If Known)	Remarks
<div><div></div><div>15F-V15 Main Column OH Receiver</div></div>	05/18/2018 10:37 AM (BILLSTRONG) ✓ BS MM	<div>Add Note</div> <div>05/18/2018 11:48 AM (BILLSTRONG) ✓ Steel cross supports show deformation</div>	05/18/2018 10:37 AM (BILLSTRONG) ✓ BS MM	05/18/2018 10:39 AM (BILLSTRONG) ✓ BS MM	05/18/2018 10:39 AM (BILLSTRONG) ✓ BS MM	05/18/2018 10:52 AM (BILLSTRONG) ✓ BS MM	<div>Add Note</div>	05/18/2018 10:53 AM (BILLSTRONG) ✓ No	05/18/2018 10:53 AM (BILLSTRONG) ✓ Yes	05/18/2018 10:53 AM (BILLSTRONG) ✓ No	<div>Add Note</div> <div>05/18/2018 11:46 AM (BILLSTRONG) ✓ There is a shallow Dent noted on the NE end of the Vessel</div>	05/18/2018 10:55 AM (BILLSTRONG) ✓ N/A	<div>Add Note</div> <div>05/18/2018 11:01 AM (BILLSTRONG) ✓ Debris/ Misc tray part on NE corner of platform-picture is on file.</div>	05/19/2018 7:30 AM (HUSKY.FCC) ✓ Assume Yes DK	05/19/2018 7:30 AM (HUSKY.FCC) ✓ Unknown DK	<div>Add Note</div>	05/18/2018 11:28 AM (HUSKY.FCC) ✓ No BM	05/18/2018 11:28 AM (HUSKY.FCC) ✓ N/A	<div>Add Note</div>

HUSKY ENERGY INC.

Waste Management Plan

2018 Superior Refinery Fire

Matt Turner

5/22/2018

Environmental Unit Leader



Signature

5-22-2018

Date

Operations Section Chief



Signature

5-22-2018

Date

Planning Section Chief



Signature

22 MAY 18

Date

Incident Commander



Signature

22 May 18

Date

Contents

Contents2

1. Objectives.....3

 1.1. Stream Identification.....3

 1.2. Stream Storage3

 1.3. Stream Management4

2. Contact Information.....4

1. Objectives

1.1. Stream Identification

A stream requiring management can range from hazardous and non-hazardous wastes to streams in which hydrocarbon can be recovered and re-refined. Once individual streams are identified, it will be paramount to keep them separate from each other. Isolating streams will ensure proper management under this plan, the site-specific Emergency Response Plan, the Incident Action Plan, and the Asbestos Remediation Plan.

1.1.1. Known streams requiring management

- Asbestos Containing Material (ACM)
- Asphalt that is mixed with ACM, debris (metal, insulation etc.), and petroleum impacted soil
- #6 fuel oil and therminol
- Product inventory remaining in units
- Waste generated during field decontamination activities (oily absorbents/PPE and decon water)
- All scoped waste from planned turnaround activities

1.1.2. Potential streams which would require management

- Chemicals from damaged containers (drums, totes, etc.)
- Any discovered or created streams (spills, new/altered work scopes, etc.)

1.2. Stream Storage

1.2.1. Wastes

Streams that are determined to be solid wastes (asphalt, debris, contaminated PPE, non-recoverable products, petroleum impacted soil, oily absorbents, etc.) will be disposed of off-site following DOT regulations as either non-hazardous waste or hazardous waste in accordance with RCRA regulations. Examples of storage containers for wastes include drums, totes, roll-off boxes and vacuum boxes. In accordance with the Asbestos Remediation Plan, all containers of ACM waste shipped off-site will be inspected by the licensed Wisconsin asbestos abatement contractor to ensure that the exteriors are asbestos free.

1.2.2. Recoverable/Recyclable Materials

Streams that are determined to be recyclable will be kept on-site in either a network of frac tanks or in the storage tank system of the facility. Frac tanks can be ordered with or without steam coils depending on what material will be stored inside them. Certain storage tanks (i.e. slop oil tanks) in the facility can also be used for the storage of streams for which hydrocarbons can be recovered but only after consulting with both the Operations Unit and Environmental Unit.

1.2.3. Water Needing Treatment

Due to the fire response efforts, a large amount of water containing firefighting foam compounds is currently present on-site that will ultimately need to be treated through the on-site Waste Water Treatment Plant (WWTP) and a granular activated carbon (GAC) system. This water is currently being stored in Ponds 2/3 & 4, the dike for tanks 106, 112 & 114, inside frac tanks, and inside Tank 45. With

the WWTP and API Separator both operating, any contaminated water can be released at the on-site wash slab for processing and treatment through the API Separator, WWTP and GAC system.

1.3. Stream Management

Once individual streams have been properly identified, the focus will then turn towards their management. All management activities are to be done in accordance with the site-specific Emergency Response Plan, the Incident Action Plan, and the Asbestos Remediation Plan. Stream management will be done on a task-specific basis in conjunction with the Operations Section, the Environmental Unit, and the Wisconsin Licensed Asbestos Abatement Contractor as necessary. Barr Engineering and GHD will coordinate the documentation of any waste disposal that occurs.

All wastes will be transported off-site according to DOT and RCRA regulations. All hazardous wastes will be disposed of at a permitted TSDF in accordance with RCRA regulations.

Streams in which hydrocarbon can be recovered are to be managed along the following guidelines:

- Slop oil tanks and frac tanks with steam coils can be used for materials to re-refined onsite
 - Flare KO material, recovered #6 fuel oil, gas oil, LCO, process de-inventory, etc.
- Frac tanks without steam coils for materials that do not require heating
 - Gasoline and diesel range products
- Tanker trucks to move material directly from the site to an off-site facility for recovery and treatment

2. Contact Information

- Waste Management Task Force Leader: Matt Turner
- Environmental Unit Leader: Dave Beattie
- Waste Water Treatment Plant Superintendent: Joe Amato
- Wisconsin Licensed Asbestos Abatement Contractors: In-Line Construction & Brandenburg

ERROR: cannot process PDF document 'Community Air Monitoring Reduction Plan.pdf'

HUSKY ENERGY INC.

Community Soot Assessment Work Plan

2018 Superior Refinery Fire

David Beattie

5/22/2018

Environmental Unit Leader  5-22-2018


Signature Date

Operations Section Chief  5-22-2018

Signature Date

Planning Section Chief  22 MAY 18

Signature Date

Incident Commander  2018/05/22

Signature Date

Community Soot Assessment Work Plan

2018 Superior Refinery Fire

Objective:

- Assess the potential deposition of soot from the fire within the surrounding community.

Approach:

- Assess property surrounding the refinery for presence/absence of soot deposition in amounts that can be visually observed, paying particular attention to flat surfaces in the area south and west of the refinery which were identified as being located downwind of the fire.
- Review visual soot assessment information generated by GHD and USEPA community monitoring teams to determine if there are any areas of visual soot deposition i) within the study area, ii) in residential/commercial/agricultural areas, iii) in locations identified through community contacts, and iv) not believed to be associated with other sources.
- Assess the need for additional steps to evaluate the potential for adverse human health effects based on the results of the above activities.

Procedure:

- Community monitoring teams will look for the presence of visible soot within the community and surrounding property as they are conducting community air quality monitoring. Observations of soot absence or presence will be made and recorded at some of the community air monitoring points with vehicles stopped (discrete soot assessment locations). While driving, crews will look for visible soot deposition throughout the community and surrounding land areas; if any visible soot is observed while traveling, the crews will stop, make further assessments, and record the observation(s). Monitoring teams will also attend locations if alerted to specific potential soot deposition by Husky through the 24-hour residents' line or through other means.
- Documentation of soot presence or absence at discrete soot assessment locations will be made using GHD's tablet data collection system. Data records will either be made as text comments on the air quality data record or as site observation records.
- Observations will also be made in areas that were not downwind during the fire to assess background soot deposition in the community and surrounding land areas, with a focus on specific depositional areas that correspond to depositional areas in the downwind areas (i.e., adjacent to roads, adjacent to rail, etc.).
- A GHD Certified Industrial Hygienist (CIH) will review the visual soot assessment information and make a determination on the potential follow-up assessment and procedures as well as the potential for adverse human health effects.
- If warranted, GHD's CIH will make recommendations for procedures to assess potential exposures to soot.